

# MAHARSHI DAYANAND UNIVERSITY ROHTAK

## NOTICE INVITING TENDER

Sealed tenders on percentage basis are invited on behalf of the Registrar, MDU, Rohtak from contractors/societies / agencies on approved list of Haryana PWD B&R / P.H. Br., MES, CPWD, autonomous bodies and other State / Centre Govt. undertakings. The tender forms will be issued to the contractors / societies / agencies up to the date of opening of tenders as mentioned against work by 12:00 Noon and will be received upto 2:00 P.M. in the office of the Registrar and opened at 3:00 P.M. on the same day in the Committee Room of Vice-Chancellor office in the presence of the tenderers or their authorized representatives, who may like to be present at that time. **The tender documents may be obtained from the office of the undersigned and the same be deposited in the office of the Registrar by the due date.**

Sr. No.	Name of work	App. Amt. (Rs. in lac)	Earnest Money (Rs.)		Cost of tender form (Rs.)	Date of opening of tender	Time limit
			Society	Contractor			
1.	Constn. of Open Drain, Footpaths, Boundary Wall, Inter Locking tiles/chequered tiles, Kerb stones, etc. at various places	25.00	25,000/-	50,000/-	5,000/-	8.10 .2012	06 months
2.	P/F of false ceiling and vitrified tiles in DDE Conference Hall and lounge	7.00	7,000/-	14,000/-	1,000/-	8.10.2012	02 months

### CONDITIONS:-

1. Complete DNIT (Detailed Notice Inviting Tender) alongwith eligibility criteria/terms & conditions and changes if any can be seen in the office of undersigned on any working day during office hours (9:00 AM to 5:00 PM) and on University Website – [www.mdurohtak.ac.in](http://www.mdurohtak.ac.in)
2. The tenderer will keep in touch with the University Web site for any change in the DNIT till the last date/revised last date of sale of tender and incorporate such changes in DNIT and the tender bids.
3. At the time of purchase of tender documents, the contractors should submit the following documents:-
  - (a) Proof of enlistment.
  - (b) Copy of PAN card.
  - (c) Copy of latest income tax return.
  - (d) Successfully work done certificates of similar nature of works during last 5 years (financial year 2007-08 to 2011-12) as under:-
    - One certificate of 80% of the estimated cost of this tender.
    - Or
    - Two certificates of 60% of the estimated cost of this tender
    - Or
    - Three certificates of 40% of the estimated cost of this tender

All the above certificates in paras 3(a) to 3(d) above will be self attested and stamped with the stamp of the firm.

4. In case tendering day happens to be a holiday, the tenders will be received / opened on next working day at the same time.
5. Validity of tender will be 90 days.
6. Earnest money is to be deposited before purchase of the tender. It should be in the shape of Demand Draft or Deposit at Call in favour of the Executive Engineer, MDU, Rohtak payable at Rohtak.
7. Contractors shall quote single percentage of rate below/above/at par on (HSR+C.P. as on Nov. 2011) on all chapters. N.S. item rates are to be quoted separately. The tender, without the rates of N.S. items, if any, in DNIT, will be rejected.
8. Conditional tender is liable to be rejected.
9. Any work, here tendered, may be withdrawn from further processing at any stage at the discretion of the competent authority without assigning any reason.
10. Nothing extra whatsoever shall be paid on account of losses, damages done by rains or any other natural calamity.
11. The tender is liable to be rejected if the tender is found in variance of the above conditions or the conditions of the DNIT.
12. Engineer-in-Charge is competent to increase / decrease the quantity of work. The contractor shall have no claim to any payment or compensation whatsoever on account of any profit or advantage which he might have derived from the execution of the work in full in case of decrease of quantity.
13. The University reserves the right to accept or reject or negotiate any of the tender or conditions/items without assigning any reason.
14. Plumbing and E.I. work shall be got done through license holder agencies for the works involving PH / E.I.
15. The agencies shall paste the cello tape on the rates quoted by them.

Executive Engineer

Endst. No. EE/ 2012 /

Dated: .09.2012

A copy of the above is forwarded to the following for information and necessary action:-

1. Superintending Engineer, PWD B&R Circles, Rohtak
2. Technical Advisor to VC, MDU, Rohtak
3. Executive Engineer, (C-II), MDUR / PWD B&R (Medical College), Rohtak / KUK / HAU. Hisar / GJU, Hisar / CDLU, Sirsa / BPS Women University, Khanpur/ DBSCRU, Murthal
4. PA to Vice-Chancellor (for kind information of the Vice-Chancellor), M. D. University, Rohtak
5. P.A. to Registrar (for kind information of Registrar), MDU, Rohtak
6. SDE(C-I, II, III) / SDE (E-I) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
7. Divisional Accountant / H.D.M., Engineering Cell, MDU, Rohtak
8. Notice Board
9. Contractor/Agency/Society: \_\_\_\_\_

Executive Engineer

## DETAILED NOTICE INVITING TENDER

**Name of work: “Construction of Open Drain, Footpaths, Boundary Wall, Inter Locking tiles/chequered tiles, Kerb stones, etc. at various places in MDU, Rohtak”**

**App. Amt. Rs. 25.00 lac**  
**Earnest Money Rs. 25,000/- Rs. 50,000/-**  
**Time Limit: 06 month**

Sr. No. / HSR	Qty.	Description	Rate(Rs.)	Unit
1/ 4.1(a)	800 cum	(a) Stone (building or pitching), sand, bajri, shingle, spalls, bricks-bats, brick ballast and stone metal (Loading and unloading)	@ Rs. 4.75 (Rs. Four and paisa seventy five only)	Per cum
2/5.2(b)	800 cum	Carriage of materials (metalled roads), lead more than 0.48 KM excluding loading, unloading and stacking. ( lead 2 KM) (b) earth work(1 KM)	@ Rs. 12/- (Rs. twelve only)	Per cum
3/6.6	100 cum	(B) (i) Earth work in Excavation of Foundations in Trenches Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches , stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction , including disposal of all surplus soil, as directed with in a leadoff 30 meters	@ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only)	Per 100 cum
4/ 11.24	150 cum	First class brick work laid in cement stone dust (from crusher) mortar 1:4 in foundation and plinth.	@ Rs. 444.65 (Rs. four hundred forty four and paisa sixty five only)	Per cum
5/10.28	75 cum	Cement concrete 1:8:16 with stone aggregate 40mm nominal size in foundation and plinth.	@ Rs. 318.65 (Rs. Three hundred eighteen and paisa sixty five only)	Per cum
6/10.26	15 cum	Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth	@ Rs. 300.20 (Rs. Three hundred & paisa twenty only)	Per cum

Contd.....2.....

Sr. No. / HSR	Qty.	Description	Rate(Rs.)	Unit
7/11.9	60 cum	1 <sup>st</sup> class brick work laid in cement sand mortar 1:4 in first storey upto 4 metres above plinth level.	@ Rs.445.60 (Rs . four hundred forty five and paisa sixty only)	Per cum
8/15.12	300 sqm	15 mm thick cement plaster 1:6 on the rough side of single or half brick wall	@ Rs. 13.10 (Rs. Thirteen & paisa ten only)	Per sqm
9/15.5	900 sqm	12 mm thick cement plaster 1:4	@ Rs. 12.70 (Rs. Twelve & paisa seventy only)	P.sqm
10/10.90+ 10.95(a)	200 cum	Cement concrete 1:1½:3 instead of cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in footings, strips, foundations, beams, rafts, pedestals and approach slabs of bridges etc., excluding steel reinforcement but including centering and shuttering, laid in position, complete in all respects, (for work upto 1.5 metres below ground level.)	@ Rs.774/- (Rs. seven hundred seventy four only)	Per cum
11/10.86 + 10.95(a)	28 cum	Cement concrete 1:1½ :3 with stone aggregate 20 mm nominal size for reinforced concrete work for walls exceeding 20 cm thickness (straight and curved) beams, girders, stairs, columns, (straight or rectangular) battens and lintels etc. excluding steel reinforcement but including centering and shuttering , laid in position, complete in all respects. (a) extra over item nos. 10.79 to 10.94, if 1: 1½:3 mix is used instead of 1:2:4	@ Rs. 1188.75 (Rs. One thousand one hundred eighty eight & paisa seventy five)	Per cum
12/15.75	600 sqm	Cement rendering on plaster 1mm thick	@ Rs. 4.25 (Rs. four and paisa twenty five only)	Per sqm
13/15.60	500 sqm	Cement pointing 1:2 deep variety on brick and tile work	@ Rs. 9.90 (Rs. Nine and paisa ninety only)	Per sqm
14/16.79	110 sqm	Providing two coats of exterior acrylic emulsion paint. (a) 2 <sup>nd</sup> quality	@ Rs. 26.85 (Rs. Twenty six and paisa eighty five only)	Per sqm

Contd.....3.....

Sr. No. / HSR	Qty.	Description	Rate(Rs.)	Unit
15/18.12	5 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors open-able or fixed stair case or parapet or any other type of railing , gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1040.35 (Rs. One thousand forty & paisa thirty five only)	Per qtl
16/24.36	150 mtr.	1.20 metres high fencing, with 1.65 metres posts, placed at every, 2.5 metres to 3 metres apart embedded in cement concrete blocks, and every tenth post, to be strutted, provided with 4 horizontal lines of G.I. barbed wire, weighing 9.34 kg. per 100 metres(minimum) and fixed with G.I. staples, tied to 6mm bar nib, with binding wire or by providing cut, including drilling holes, in the post complete (excluding the cost of posts, struts, earth work and concrete which is payable extra)	@ Rs. 5.25 (Rs. five and paisa twenty five only)	Per mtr.
17/10.39	38 cum	Cement concrete 1:4:8 with stone aggregate 40 mm nominal size in foundation and plinth.	@ Rs. 403.10 (Rs. four hundred three and paisa ten only)	Per cum
18/10.41	38 cum	Cement concrete 1:2:4 with stone aggregate 20 mm nominal size in foundation and plinth	@ Rs. 615.60 (Rs. Six hundred fifteen & paisa sixty only)	Per cum
19/10.158	300 sqm	Providing and laying 60mm thick interlocking paver blocks of all shapes and colours in design mix cement M-35 over a bed of 25mm thick fine sand complete in all respects.	@ Rs. 350/- (Rs. Three hundred fifty only)	Per sqm
20/14.45	30 sqm	Precast chequered tiles of 20mm thickness in ordinary grey cement without chips laid on 20mm thick bed of cement coarse sand mortar 1:3 with neat cement slurry between joints and over the base in floors, treads of steps and landings.	@ Rs. 101.35 (Rs. One hundred one and paisa thirty five only)	Per sqm
21/16.9	50 sqm	Applying priming coat with metal primer on new steel or iron work including preparation of surfaces	@ Rs. 2.95 (Rs. Two & paisa ninety five only)	Per sqm

Sr. No. / HSR	Qty.	Description	Rate(Rs.)	Unit
22/16.3	50 sqm	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	@ Rs. 8.05 (Rs. Eight & paisa five only)	Per sqm
23/10.77	18 cum	Precast cement concrete 1:2:4 with stone aggregate 20mm nominal size in Kerbs and the like items, finished smooth with 6mm thick cement plaster 1:3 on exposed surface including form work, placing and fixing in position, complete at the ground level or in first storey.	@ Rs. 942.50 (Rs. Nine hundred forty two and paisa fifty only)	Per cum
24/18.22	70 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. Nine hundred seventeen & paisa five only)	Per qtl.
25/13.89(a)	40 mtr.	Providing and fixing PVC rain water pipe 6 kg. pressure of ISI mark in cement mortar during masonry work. (a) 100mm dia PVC pipe 6 kg. pressure	@ Rs. 182/- (Rs. one hundred eighty two only)	Per mtr.
26/NS	50 cum	S/Filling tibba sand including watering. Compaction , consolidation etc complete to the entire satisfaction of Engineer-in-charge.	Rate quoted by the contactor	Per cum

## DETAILED NOTICE INVITING TENDER

**Name of work: “Providing and fixing false ceiling and vitrified tiles in DDE Conference Hall and Lounge in MDU, Rohtak”**

**App. Amt. Rs. 7.00 lac**

**Earnest Money Rs 7,000/- / Rs. 14,000/-**

**Time Limit: 02 months**

Sr. No. / HSR	Qty.	Description	Rate(Rs.)	Unit
1/13.91	11.00 sqm	Providing and fixing false ceiling with 12mm thick Gypsum Board fixed on M.S. steel runners frame including cost of screws angles, cleats, rawel pugs, with taping, filling with Gypsum compound and applying priming coat etc. complete in all respects.	@ Rs. 600/- (Rs. six hundred only)	Per sqm
2/13.93	401 sqm	Providing and fixing false ceiling with grooves with 12mm to 15mm thick, 600mmx600mm best quality mineral fibre tiles of approved make fixed on M.S. steel runners frame i/c cost of screws angles, cleats, rawel plugs, with taping and painting, etc. complete in all respects as approved by the Engineer-in-Charge.	@ Rs. 800/- (Rs. Eight hundred only)	Per sqm
3/14.90	4 sqm	Providing and fixing vitrified tiles of size 600 x 600mm of approved make in flooring laid in any pattern as specified over base of 12mm thick cement coarse sand mortar 1:3 and jointed with white cement slurry mixed with pigment to match the shade to tiles. Note : Tile shall be of premium quality (1 <sup>st</sup> quality) of reputed manufacturer like NITCO, KAJARIA, SOMANI, ORIENT & JOHNSONS	@ Rs. 929.80 (Rs. Nine hundred twenty nine and paisa eighty only)	Per sqm
4/14.97	100 sqm	Laying and fixing ceramic & glazed tiles /vitrified tiles/of any size of approved make in floors/dados, laid in any pattern as specified over base of 3mm thick adhesive of reputed brands such as Pidilite, Laticrete, Ferrouscrete & Valendure as per IS specification 15477-2004 using 5 kg. adhesive per sqm area of tiles and jointed with white cement slurry mixed with pigment to match the shade of tiles excluding cost of tiles	@ Rs. 347/- (Rs. three hundred forty seven only)	Per sqm

Contd...P/2..

Sr. No. / HSR	Qty.	Description	Rate(Rs.)	Unit
5/16.60	250 sqm	Distempering with washable oil bound distemper (of approved manufacture two coats on old distempered work.	@ Rs. 6/- (Rs. six only)	Per sqm
6/16.7	60 sqm	Painting one coats with synthetic enamel paint in all shades on old wood-work or metallic or plastered or concrete surfaces to give an even shade including rubbing down old paint	@ Rs. 4.05 (Rs. four and paisa five only)	Per sqm
7/NS	110 sqm	Supply of vitrified tile of Kajaria make as per required shed and as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per sqm
8/NS	315 sqm	Removing of existing false ceiling of wooden frame and removing of material as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per sqm
9/NS	123 sqm	Wall paneling of 12mm thick ply wood with 1mm thick sunmica fixed on G.I. stud complete as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per sqm