

DETAILED NOTICE INVITING TENDER

Name the work "Construction/laying of new Sewer line in the campus of UILMS, Gurgaon.

App. Amt. Rs. 5,95,000/-
Earnest Money Rs. 5,950/- / 11,900/-
Time Limit: 01 month

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/6.10 (a)	266.61 cum	Excavation of trenches in streets, lanes or in open areas for storm sewer, sewers running by gravity and manholes to full depths as shown in drawings including shoring, timbering of poling boards, frame system type, dressing to correct sections and dimensions, according to templates and levels, dewatering, provision for diversion of traffic, cutting trees and bushes etc night signals, profiles, pegs, sight rails, bonding rods crossing over trenches for access to the houses, watching , fencing etc. fixing and maintenance of caution boards, refilling of trenches, watering of refill, in 15 cm layers, ramming and restoration of unmetalled or unpaved surface to original site of work upto a lead of 1 KM in ordinary soil. (a) for depths of excavation not exceeding 3 meters below ground level	@ Rs. 1189.00 (Rs one thousand one hundred eighty nine only)	P.100 cum
2/10.39	40.92 cum	Cement concrete 1:4:8 with stone aggregate 40 mm nominal size in foundation and plinth.	@ Rs. 403.10 (Rs. four hundred three and paisa ten only)	Per cum
3/29.95 (d)	293.83 mtr	Providing, salt glazed stone ware pipes grade 'A' in standard length of 600mm each pipe marked with IS:651 and their lowering, cutting, jopinting and testing as described in HSR 29.38, 29.39, 29.40 including the cost of jointing materials as well as carriage, loading, unloading, stacking, handling, re-handling etc. complete in all respects to the satisfaction to the Engineer-in-Charge. (d) 250mm i/d	@ Rs. 386/- (Rs. three hundred eighty six only)	Per mtr.

Contd....2...

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
4/10.41	58.93 cum	Cement concrete 1:2:4 with stone aggregate 20 mm nominal size in foundation and plinth	@ Rs. 615.60 (Rs. Six hundred fifteen & paisa sixty only)	Per cum
5/29.84 (c)	20 nos.	Constructing brick masonry inspection chamber size as given below upto 0.60 metre average depth in cement mortar 1:5 lime concrete with 40 percent lime mortar 2:3 in foundation cement concrete 1:2;4 benching 12 mm thick cement plaster 1:2 with a floating coat of 1 mm thick of neat cement RCC1:2:4 slab 100 mm thick/C.C. topping, 50 mm thick with 455 mm x 455 mm/455mmx610 mm inside light duty C.I. inspection chamber cover and frame weight as per I.S. specification painted with 3 coats of black bitumastic superior paint complete as per standard design. (c) size 600 mm x 900 mm inside (with 455 mm x 455 mm cover and frame light duty single seal weighing 20 kg with RCC slab)	@ Rs. 690.00 (Rs. Six hundred ninety only)	Each
6/29.85 (c)	12 mtr	Extra for every 0.30 metre depth of inspection chamber (c) 600 mm 900 mm	@ Rs. 139.00 (Rs. One hundred thirty nine only)	Per 0.30 metre depth
7/24.37	72.46 sqm	Dismantling of Road including soling and wearing coat, screening and stacking of old serviceable material, complete in all respect	@ Rs. 296.70 (Rs. two hundred ninety six and paisa seventy only)	Per 100 sqm
8/10.132	11.04 cum	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in pavement, roads, taxi-tracks and run ways, laid to required slope and camber, including consolidation, finishing and tamping complete	@ Rs. 642.40 (Rs. six hundred forty two and paisa forty only)	Per cum