

## DETAILED NOTICE INVITING TENDER

Name the work “Construction of Shed with fibre sheet roofing and kota stone flooring in Stadium in M.D.U, Rohtak”

**App. Amt. Rs. 1,31,000/-**  
**Earnest Money Rs. 1,310/- / 2,620/-**  
**Time Limit: 01 month**

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/6.6	1.41 cum	Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches , stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction , including disposal of all surplus soil, as directed with in a leadoff 30 meters	@ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only)	Per 100 cum
2/10.26	4.34 cum	Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth	@ Rs. 300.20 (Rs. Three hundred & paisa twenty only)	Per cum
3/11.3	1.27 cum	First class brick work laid in cement sand mortar 1:5 in foundation and plinth.	@ Rs. 407.60 (Rs. Four hundred seven and paisa sixty only)	Per cum
4/11.48(a)	4.46 sqm	(a) 11.43 cm thick brick wall laid in cement sand mortar 1:4 in superstructure	@ Rs. 55.10 (Rs. Fifty five & paisa ten only)	Per sqm
5/11.8	4.24 cum	First class brick work laid in cement sand mortar 1:5 in first storey upto 4 metres above plinth level.	@ Rs. 428.60 (Rs. Four hundred twenty eight and paisa sixty only)	Per cum
6/10.114	4.18 sqm	Damp proof course 40 mm thick of cement concrete 1:2:4 using stone aggregate 20 mm nominal size with 2 coats of bitumen 20/30 penetration at 1.65 Kg per sqm laid hot and sanded	@ Rs. 35.05 (Rs. Thirty five & paisa five only)	Per sqm
7/15.6	33.47 sqm	12mm thick cement plaster 1:5	@ Rs. 11.60 (Re. Eleven and paisa sixty only)	Per sqm

Contd. Next Page

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
8/15.11	18.58 sqm	15mm thick cement plaster 1:5 on the rough side of single or half brick wall.	@ Rs. 14.25 (Rs. Fourteen and paisa twenty five only)	Per sqm
9/10.41	0.89 cum	Cement concrete 1:2:4 with stone aggregate 20 mm nominal size in foundation and plinth	@ Rs. 615.60 (Rs. Six hundred fifteen & paisa sixty only)	Per cum
10/18.41	1.188 qtl.	Providing steel pipe ISI mark in columns with 2 nos. M.S. plates welded on both ends of the pipe including cutting etc. complete fixed in position.	@ Rs. 1,205.35 (Rs. One thousand two hundred five and paisa thirty five only)	Per qtl.
11/18.12	4.13 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors open-able or fixed stair case or parapet or any other type of railing, gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1040.35 (Rs. One thousand forty & paisa thirty five only)	Per qtl.
12/14.62	46.45 sqm	Kota stone flooring 34 mm to 40mm thick in any pattern as specified over 12mm thick base of cement coarse sand mortar 1:3 laid and jointed with neat cement slurry mixed with pigment to match the shade of stone including rubbing and polishing	@ Rs. 201.95 (Rs. Two hundred one and paisa ninety five only)	Per sqm
13/10.81	0.59 cum	Cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in Shelves excluding steel reinforcement, but including centering and shuttering, laid in position, complete in all respects.	@ Rs. 947.70 (Rs. Nine hundred forty seven and paisa seventy only)	Per cum
14/18.22	0.73 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. Nine hundred seventeen & paisa five only)	Per qtl.
15/N.S.	432 sft.	Providing and fixing 2 mm thick fibre sheet including J Hooks & Nut Bolts etc. complete to the entire satisfaction of the Engineer-in-Charge.	Rate to be quoted by the contractor	Per sft.