

DETAILED NOTICE INVITING TENDER

Name of the work “Repair and maintenance of water coolers installed at various buildings in, MDU Campus, Rohtak”

App. Amt. Rs. 1,90,000/-
Earnest Money Rs.1,900/- / 3,800/-
Time Limit: 6 months

Sr. No./N.S.	Qty.	Description	Rate to be quoted by the contractor	Unit
1.	30 nos.	Providing and fixing relay of water cooler ‘Hytec/Denforce’ make including material and labour charges		Each
2.	40 nos.	Providing and fixing starting capacitor ‘Tipcon/Telcon’ make including material and labour charges		Each
3.	40 nos.	Providing and fixing running capacitor ‘Tipcon/Telcon’ make including material and labour charges		Each
4.	30 nos.	Providing and fixing thermostat ‘Annpurna/Danfoss’ make including material and labour charges		Each
5.	20 nos.	Providing and fixing over load ‘THK/Danfoss’ make including material and labour charges		Each
6.	20 nos.	Providing and fixing brass tap/push tap ‘Sieko’ make including material and labour charges		Each
7.	10 nos.	Providing and fixing new compressor ‘Kirloskar’ make including material and labour charges		Each
8.	10 nos.	Providing and fixing fan motor ‘GEC/Cool Home’ make including material and labour charges		Each
9.	20 nos.	Rewinding of compressor stator including material and labour charges		Each
10.	20 nos.	Providing and fixing bush of compressor ‘MSP’ including material and labour charges		Each
11.	10 nos.	Providing and fixing piston and sleeve in compressor ‘MSP’ including material and labour charges		Each
12.	10 nos.	Providing and fixing crank shaft and connecting rod ‘JK’ make including material and labour charges		Each
13.	20 nos.	Providing and fixing capillary pipe (copper) ‘Annpurna’ make including material and labour charges		Each
14.	10 nos.	Refilling of gas ‘R-22’ and testing of air pressure including material and labour charges		Each

Contd....P/2....

Sr. No./N.S.	Qty.	Description	Rate to be quoted by the contractor	Unit
15.	10 nos.	Providing and fixing main lead 23 x 76 'Plaza' make of required length including material and labour charges		Each
16.	20 nos.	Providing and fixing 15 amp. three pin top 'Anchor/SK' make including material and labour charges		Each
17.	05 nos.	Painting of water cooler with synthetic enamel paint (2 coat) 'Asian' make including material and labour charges		Each
18.	80 nos.	Servicing and cleaning of water cooler including material and labour charges		Each
19.	30 nos.	Rickshaw / carriage charges both side		Each
20.		Scrap Value of dismantled/unserviceable compressors		Each
21.		Scrap Value of dismantled/unserviceable motors		Each

Note: (1) The rate is to be quoted by the agency should be inclusive of unserviceable material for sr. no. 1 to 18.

(2) All above items shall be executed to the entire satisfaction of Engineer-in-charge.