

MAHARSHI DAYANAND UNIVERSITY ROHTAK
NOTICE INVITING TENDER

Sealed tenders on percentage basis are invited on behalf of the Registrar, MDU, Rohtak from Co-Operative L/C Societies, contractors on approved list of Haryana PWD B&R / P.H. Br., MES/CPWD/autonomous bodies and other State/Centre Govt. undertakings. The tender forms will be issued to the tenderers for both works from the date of publication till 12.00 Noon on the date of opening of respective tender of concerned agency (i.e. Society or contractor) and will be received upto 2.00 PM on the same date. The tenders will be opened on the same day at 2.30 PM in the Committee Room of Vice-Chancellor in the presence of tenderers or their authorized representatives, who may like to be present. If less than 3 tenders are received from societies for work at Sr.No.2 & 3, then tenders to societies will be sold again till 12.00 noon next day i.e. date of opening for contractors and tenders will be opened alongwith the tenders of contractors. **The tender documents may be obtained from the office of the Executive Engineer and the same be deposited in the box kept in the office of the Registrar by the due date and time.**

| Sr. No. | Name of work | App. Amt. (Rs.) | Earnest Money (Rs.) | | Cost of tender form (Rs.) | Date of opening of tender | | Time of completion |
|---------|---|-----------------|---------------------|------------|---------------------------|---------------------------|------------|--------------------|
| | | | Society | Contractor | | Society | Contractor | |
| 1. | Special Repair, White Washing, Painting, Apex etc. in various Type of houses | 43,00,000/- | 43,000/- | 86,000/- | 5000/- | 10/06/2011 | 10/06/2011 | 12 months |
| 2. | Construction of open drain, footpaths, boundary walls, interlocking tile, kerb stone etc. at various places in MDU Campus | 25,00,000/- | 2000/- | 50,000/- | 1000/- | 9/6/11 | 10 /6/11 | 12 Months |
| 3 | Providing and Fixing 5" long G.I. fasteners in Red Agra stone lining of various faculties (Law, IMSAR, New Arts Faculty) | 6,70,000/- | 2000/- | 13400/- | 1000/- | 9/6/11 | 10/6/11 | 03 Months |

CONDITIONS:-

1. DNIT can be seen in the office of undersigned on any working day during office hours (9.00AM to 5.00 PM). For any query may contact on Mobile No. 9416401254.
2. In case tendering day happens to be a holiday, the tenders will be received / opened on next working day at the same time.
3. Earnest money is to be deposited before purchase of the tender. It should be in the shape of Demand Draft or Deposit at Call in favour of the Executive Engineer, MDU, Rohtak payable at Rohtak.
4. Contractors will quote percentage of rate below/above on (HSR+C.P.) for chapters of HSR as given in notes of DNIT. N.S. item rates are to be quoted separately other wise tender is liable to be rejected.

Contd..P/2

5. At the time of purchase of tenders, the contractors should bring with them, proof of enlistment with copy of PAN card and one successfully work done certificate (similar nature) of 80% of the estimated cost of this tender during the last two years (Financial Year 2009-10 & 2010-11) or two successfully work done certificates (similar nature) of 60% of the estimated cost of this tender during the last two years (Financial Year 2009-10 & 2010-11). Copy of latest income tax return will also be submitted.
6. Conditional Tender is liable to be rejected.
7. Any work, here tendered, may be withdrawn from further processing at any stage at the discretion of the competent authority without assigning any reason.
8. Nothing extra whatsoever shall be paid on account of losses, damages done by rains or any other natural calamity.
9. Plumbing and E.I. work shall be got done through license holder agencies for works involving PH / E.I.
10. The contractors/agencies shall paste the cello tape on the rates quoted by them.
11. The tender is liable to be rejected if the tender is found in variance of the above conditions or the conditions of the DNIT.
12. The university reserves the right to accept or reject or negotiate any of the tender or conditions/items without assigning any reason.
13. Notice inviting tender and amendments, if any can be seen at university web site - www.mdurohtak.ac.in

Executive Engineer

Endst. No. EE/ 2011 /

Dated:

A copy of the above is forwarded to the following for information and necessary action:-

1. Technical Advisor to VC, MDU, Rohtak
2. Superintending Engineer, PWD B&R Circles, Rohtak
3. Executive Engineer, PWD B&R (Medical College), Rohtak
4. Executive Engineer, KUK / HAU. Hisar / GJU, Hisar / CDLU, Sirsa
5. Secretary to Vice-Chancellor (for kind information of worthy Vice-Chancellor), M.D.U, Rohtak
6. P.A. to Registrar (for kind information of Registrar), MDU, Rohtak
7. SDE(C-I, II, III) / SDE (E-I, II) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
8. Divisional Accountant / H.D.M., Engineering Cell, MDU, Rohtak
9. Notice Board
10. Contractor/Agency/Society: _____

Executive Engineer

DNIT for the work “Special repair, white washing, painting, APEX etc. in various Type of houses in MDU, Rohtak”

App. Amt. Rs. 43,00,000/-

Earnest Money : Rs. 86,000/- / Rs. 43,000/-

Time Limit: 6 months

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|-----------|---|--|---------|
| 1/16.46 | 67373 sqm | (G) White Washing One coat or subsequent coat | @ Rs. 0.55 (Paisa fifty five only) | Per Sqm |
| 2/16.47 | 7485 sqm | (G) White Washing Two coats | @ Rs. 0.90 (Paisa ninety only) | Per Sqm |
| 3/16.59 | 32297 sqm | Distempering with washable oil bound distemper of approved manufacturer one coat on old distempered work | @ Rs. 3.35 (Rs. three and paisa thirty five only) | Per Sqm |
| 4/16.60 | 3485 sqm | Distempering with washable oil bound distemper of approved manufacturer two coat on old distempered work | @ Rs. 6.00 (Rs. six only) | Per sqm |
| 5/16.5 | 1672 sqm | Painting two coats with synthetic enamel paint in all shades on old wood-work or metallic or plastered or concrete surfaces to give an even shade including rubbing down old paint. | @ Rs. 7.15 (Rs. Seven and paisa fifteen only) | Per sqm |
| 6/16.7 | 22677 sqm | Painting one coats with synthetic enamel paint in all shades on old wood-work or metallic or plastered or concrete surfaces to give an even shade including rubbing down old paint | @ Rs. 4.05 (Rs. four and paisa five only) | Per sqm |
| 7/15.6 | 1326 sqm | 12mm thick cement plaster 1:4 | @ Rs. 11.60 (Re. eleven and paisa sixty only) | Per sqm |
| 8/15.11 | 1760 sqm | 15mm thick cement plaster :5 on the rough side of single or half brick wall. | @ Rs. 14.25 (Rs. fourteen and paisa twenty five only) | Per sqm |

Contd...P/2....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|----------|---|--|---------|
| 9/14.10 | 450 sqm | Conglomerate floor 50mm thick cement concrete topping 1:2:4. | @ Rs. 37.60 (Rs. thirty seven and paisa sixty only) | Per Sqm |
| 10/13.14 | 250 sqm | Tile terracing with one layer of tiles, 22.86 cm x 11.43 cm x 3.81 cm laid dry over a layer of mud mortar including grouting with cement sand mortar 1:3 and top surface to be left clean. | @ Rs. 36.40 (Rs. thirty six and paisa forty only) | Per sqm |
| 11/15.71 | 4420 sqm | Cement pointing 1:2 flush on flat brick flooring. i) 1 st storey | @ Rs. 5.90 (Rs. five and paisa ninety only) | Per sqm |
| 12/17.79(b) | 50 nos. | Providing and fixing helical door spring 150 mm (superior quality) including necessary screws, complete. (b) iron | @ Rs. 23.85 (Rs. twenty three and paisa eighty five only) | Each |
| 13/17.36 | 125 sqm | Supplying and fixing glass panes with moulding of commercial hard wood such as hollock, champ, chikrassy and chaplash etc.(non coniferous timber other than teak, conforming to I.,S. specification No.1003, kiln seasoned) (b) 3mm thick (glazing area above 9 sq dm, but upto 55 sq dm of each pane) | @ Rs. 114.05 (Rs. one hundred fourteen and paisa five only) | Per sqm |

Contd..P/3....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|-----------|--|---|---------|
| | 100 sqm | (c) 4mm thick (glazing area above 55 sq dm but upto 84 sq dm of each pane) | @ Rs. 126.50 (Rs. one hundred twenty six and paisa fifty only) | Per Sqm |
| 14/18.30 | 125 sqm | Supplying & fixing glass panes including special metal sash putty of approved make. (a) glass panes 3 mm thick exceeding 40 sqdm area | @ Rs. 97.50 (Rs. ninety seven and paisa fifty only) | Per sqm |
| | 100 sqm | (b) glass panes 4 mm thick exceeding 40 sqdm area | @ Rs. 115.40 (Rs. one hundred fifteen and paisa forty only) | Per Sqm |
| 15/16.25 | 52819 sqm | Applying primer coat with cement primer in all shades on newly plastered or concrete exterior surfaces. | @ Rs. 4.15 (Rs. four and paisa fifteen only) | Per sqm |
| 16/15.71 | 695 sqm | Cement pointing 1:2 flush on flat brick flooring. i) ^{3rd} storey | @ Rs. 6.26 (Rs. six and paisa twenty six only) | Per sqm |
| 17/11.3 | 8 cum | First class brick work laid in cement sand mortar 1:5 in foundation and plinth. | @ Rs. 407.60 (Rs. four hundred seven and paisa sixty only) | Per cum |

Contd...P/4....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|--|---|---|----------------------------------|
| 18/16.79 | 26410 sqm | Providing two coats of exterior acrylic emulsion paint where directed by Engineer-in-Charge. b) 1 st quality. | @ Rs. 48.75 (Rs. Forty eight and paisa seventy five only) | Per sqm |
| 19/18.34 | 200 mtr. 120 mtr. 125 mtr. | Pressed steel sheet frames (chowkats) consisting of 2 mm thick steel sheet of the specified section, including iron lugs (hold fasts), iron hinges, conforming to PWD specifications, including bolts for fixing stops lockmotch, provision for receiving tower bolts and finished with one coat of ready-mixed paint red lead non setting primer, of approved quality, fixed in position including the cost of cement concrete 1:3:6 for filling in the frame and cement concrete 1:3:6 for lugs complete:- (a) door & window frames of size 89 mm x 50 mm with 40 mm wide single rebate (b) door & window frames of size 76 mm x 38 mm with 35 mm wide single rebate (c) door & window frames of size 127 mm x 50 mm with 40 mm wide single rebate | @ Rs. 71.55 (Rs. Seventy one & paisa fifty five only) @ Rs. 58.50 (Rs. Fifty eight and paisa fifty only) @ Rs. 76.80 (Rs. Seventy six and paisa eighty only) | Per mtr. Per mtr. Per mtr. |

Contd...P/5...

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|---------|---|---|----------|
| 20/18.12 | 02 qtl. | Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors open-able or fixed stair case or parapet or any other type of railing , gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position | @ Rs. 1040.35 (Rs. One thousand forty & paisa thirty five only) | Per qtl. |
| 21/17.90(a) | 36 sqm | Factory manufactured paneled door or glazed window, shutters of commercial hard wood such as hollock, champ, chikrassy and chaplash etc. (non coniferous timber other than teal , conforming to I.S. specification No.1003, kiln seasoned) with 100 mm wide vertical styles, 150 mm wide lock rail, 200 mm wide bottom rail and 100 mm wide other rails, with panels of 15 mm thick , tongued and grooved of commercial hard wood and including cost of iron hinges, screws, chocks/cleats, stops, nails etc., complete fixed in position (excluding the cost of any fittings, other than specified above, but including labour for fixing the same in position)- (a) 30 mm thick NOTE : The wood will be used of Hollock, Champ, chikrassy and chaplash only | @ Rs. 398.15 (Rs. Three hundred ninety eight & paisa fifteen only) | Per sqm |

Contd...P/6....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|--------------------------------------|----------------------|--|---|--------------------------------|
| 22/17.93(a)- Note (i) of 17.18 | 40 sqm 80 sqm | Factory manufacture solid flush door shutter with block board core as per I.S. no. 1659-1969 boarded with water proof type phenol formaldehyde synthetic resin hot pressed conforming to IS 2202 part-I and part II, fixed in position, including iron hinges, screws, chocks/cleats and stops etc (excluding the cost of any fittings other than specified above , but including labour for fixing the same in position) (a) commercial veneering with vertical grains or cross bands and face veneer on both sides commercial facing with laminated core and lipped edges:- (i) 5 mm thick (iii) 35mm thick | @ Rs. 387.15 (Rs. Three hundred eighty seven and paisa fifteen only) @ Rs. 436.15 (Rs. Four hundred thirty six and paisa fifteen only) | Per sqm Per sqm |
| 23/17.92 – note of 17.18 | 20 sqm | Factory manufactured wire gauze door and window, shutters of commercial hard wood such as hollock, champ, chikrassy and chaplash etc. (non coniferous timber other than teak, conforming to I.S. specification No.1003, kiln seasoned) with 100 mm wide vertical styles, 150 mm wide lock rail, 200 mm wide bottom rail and wire gauze of 140 G or 120 G designation including cost of iron hinges, screws, chock/cleats, stops nails etc., complete fixed in position (excluding the cost of any fittings, other than specified above but including labour for fixing the same in position) (i) 30mm thick | @ Rs. 310.40 (Rs. three hundred ten and paisa forty only) | Per sqm |

Contd....P/7.....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|-----------|---|--|---------|
| | 40 sqm | (i) 35mm thick NOTE : The wood will be used of Hollock, Champ, chikrassy and chaplash only | @ Rs. 335.70 (Rs. Three hundred thirty five and paisa seventy only) | Per sqm |
| 24/17.87 | 40 sqm | Providing and fixing 0.50 mm thick aluminum sheet, including cost of necessary screws, etc. complete. | @ Rs. 90.55 (Rs. Ninety and paisa fifty five only) | Per sqm |
| 25/17.71 | 146 sqm | Cost of iron fittings, complete for doors and windows, such as tower bolts, handles, etc., and screws for these fittings (excluding sliding bolt)- (a) or single leaf shutter | @ Rs. 6.40 (Rs. Six and paisa forty only) | Per sqm |
| 26/8.32(a) | 52819 sqm | To prepare surfaces by scraping, brushing to remove Tera Kota/Snowcem as per entire satisfaction of Engineer-in-Charge. | @ Rs. 0.45 (Paisa forty five only) | Per sqm |
| 27/NS | 26409 sqm | Providing one coat of exterior acrylic emulsion paint to entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per sqm |

- NOTE :-**
1. The contractor will quote one single rate below/above (HSR+CP) for all items covered under all chapter of HSR of civil work.
 2. The contractor will quote also apart from above on single rate below/above (HSR+CP) for items covered under chapter no. 28 & 30 of HSR for Public Health work.
 3. The contractor will quote also apart from above on single rate below/above (HSR+CP) for items covered under chapter no. 31 of HSR for Electrical work.
 4. Rate of any item not covered in HSR or in DNIT will be finalized as per the prevailing market rates as NS item.
 5. Removal of vegetation/small trees/their roots etc. from walls/roofs/parapets etc. is included in the above relevant rates. Nothing extra shall be paid on this account.

DNIT for the work “Construction of open drain, footpaths, boundary wall, interlocking tiles, kerb stone etc. at various places in MDU, Rohtak”

App. Amt. Rs. 25,00,000/-

Earnest money Rs. 50,000/-

Rs. 2,000/-

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|---------|---|---|-----------|
| 1/ 4.1 | 800 cum | (a) stone (building or pitching), sand, bajri, shingle, spalls, brick-bats, brick ballast and stone metal (Loading and unloading) | @ Rs. 4.75 (Rs. four and paisa seventy five only) | Per cum |
| 2/5.2(b) | 800 cum | Carriage of materials (metalled roads), lead more than 0.48 KM excluding loading, unloading and stacking. Upto 1 KM (b) Earth work | @ Rs. 12/- (Rs. twelve only) | Per cum |
| 3/6.6 | 100 cum | Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches , stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction , including disposal of all surplus soil, as directed with in a leadoff 30 meters | @ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only) | Per % cum |
| 4/11.24 | 200 cum | First class brick work laid in cement stone dust (from crusher) mortar 1:4 in foundation and plinth. | @ Rs. 444.65 (Rs. four hundred forty four and paisa sixty five only) | Per cum |
| 5/10.28 | 105 cum | Cement concrete 1:8:16 with stone aggregate 40mm nominal size in foundation and plinth. | @ Rs. 318.65 (Rs. three hundred eighteen and paisa sixty five only) | Per cum |

Contd....P/2....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|------------------------|----------|---|---|---------|
| 6/10.26 | 20 cum | Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth | @ Rs. 300.20 (Rs. Three hundred & paisa twenty only) | Per cum |
| 7/11.29 | 60 cum | First class brick work laid in cement, stone dust (from crusher) mortar 1:4 in first storey upto 4 metres above plinth leve. | @ Rs. 465.65 (Rs. Four hundred sixty five and paisa sixty five only) | Per cum |
| 8/15.12 | 300 sqm | 15 mm thick cement plaster 1:6 on the rough side of single or half brick wall | @ Rs. 13.10 (Rs. Thirteen & paisa ten only) | Per sqm |
| 9/15.5 | 1200 sqm | 12 mm thick cement plaster 1:4 | @ Rs. 12.70 (Rs. Twelve & paisa seventy only) | P.sqm |
| 10/10.90+ 10.95(a) | 25 cum | Cement concrete 1:1½:3 instead of cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in footings, strips, foundations, beams, rafts, pedestals and approach slabs of bridges etc., excluding steel reinforcement but including centering and shuttering, laid in position, complete in all respects, (for work upto 1.5 metres below ground level.) | @ Rs.774.00 (Rs. seven hundred seventy four only) | Per cum |
| 11/10.86 + 10.95(a) | 38 cum | Cement concrete 1:1½ :3 with stone aggregate 20 mm nominal size for reinforced concrete work for walls exceeding 20 cm thickness (straight and curved) beams, girders, stairs, columns, (straight or rectangular) battens and lintels etc. excluding steel reinforcement but including centering and shuttering , laid in position, complete in all respects. (a) extra over item nos. 10.79 to 10.94, if 1: 1½:3 mix is used instead of 1:2:4 | @ Rs. 1188.75 (Rs. One thousand one hundred eighty eight & paisa seventy five) | Per cum |

Contd...P/3.....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|----------|---|--|----------|
| 12/15.75 | 600 sqm | Cement rendering on plaster 1mm thick | @ Rs. 4.25 (Rs. Four and paisa twenty five only) | Per sqm |
| 13/15.60 | 500 sqm | Cement pointing 1:2 deep variety on brick and tile work | @ Rs. 9.90 (Rs. Nine and paisa ninety only) | Per sqm |
| 14/16.79 | 110 sqm | Providing two coats of exterior acrylic emulsion paint. (a) nd quality | @ Rs. 26.85 (Rs. Twenty six and paisa eighty five only) | Per sqm |
| 15/18.12 | 5 qtl. | Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors open-able or fixed stair case or parapet or any other type of railing , gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position | @ Rs. 1040.35 (Rs. One thousand forty & paisa thirty five only) | Per qtl |
| 16/24.36 | 150 mtr. | 1.20 metres high fencing, with 1.65 metres posts, placed at every, 2.5 metres to 3 metres apart embedded in cement concrete blocks, and every tenth post, to be strutted, provided with 4 horizontal lines of G.I. barbed wire, weighing 9.34 kg. per 100 metres(minimum) and fixed with G.I. staples, tied to 6mm bar nib, with binding wire or by providing cut, including drilling holes, in the post complete (excluding the cost of posts, struts, earth work and concrete which is payable extra) | @ Rs. 5.25 (Rs. five and paisa twenty five only) | Per mtr. |
| 17/10.39 | 38 cum | Cement concrete 1:4:8 with stone aggregate 40 mm nominal size in foundation and plinth. | @ Rs. 403.10 (Rs. four hundred three and paisa ten only) | Per cum |

Contd...P/4....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|---------|--|---|----------|
| 18/10.41 | 38 cum | Cement concrete 1:2:4 with stone aggregate 20 mm nominal size in foundation and plinth | @ Rs. 615.60 (Rs. Six hundred fifteen & paise sixty only) | Per cum |
| 19/10.158 | 300 sqm | Providing and laying 60mm thick interlocking paver blocks of all shapes and colours in design mix cement M-35 over a bed of 25mm thick fine sand complete in all respects. | @ Rs. 350/- (Rs. Three hundred fifty only) | Per sqm |
| 20/14.45 | 30 sqm | Precast chequered tiles of 20mm thickness in ordinary grey cement without chips laid on 20mm thick bed of cement coarse sand mortar 1:3 with neat cement slurry between joints and over the base in floors, treads of steps and landings. | @ Rs. 101.35 (Rs. One hundred one and paise thirty five only) | Per sqm |
| 21/16.9 | 50 sqm | Applying priming coat with metal primer on new steel or iron work including preparation of surfaces | @ Rs. 2.95 (Rs. Two & paise ninety five only) | Per sqm |
| 22/16.3 | 50 sqm | Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade. | @ Rs. 8.05 (Rs. Eight & paise five only) | Per sqm |
| 23/10.77 | 18 cum | Precast cement concrete 1:2:4 with stone aggregate 20mm nominal size in Kerbs and the like items, finished smooth with 6mm thick cement plaster 1:3 on exposed surface including form work, placing and fixing in position, complete at the ground level or in first storey. | @ Rs. 942.50 (Rs. Nine hundred forty two and paise fifty only) | Per cum |
| 24/18.22 | 98 qtl. | Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete | @ Rs. 917.05 (Rs. Nine hundred seventeen & paise five only) | Per qtl. |

Contd...P/5.....

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|---------|--|--|----------|
| 25/13.89(a) | 40 mtr. | Providing and fixing PVC rain water pipe 6 kg. pressure of ISI mark in cement mortar during masonry work. (a) 100mm dia PVC pipe 6 kg. pressure | @ Rs. 182/- (Rs. one hundred eighty two only) | Per mtr. |
| 26/NS | 380 cum | S/Filling tibba sand including watering. Compaction , consolidation etc complete to the entire satisfaction of Engineer-in-charge. | Rate quoted by the contactor | Per cum |

NOTE:-

1. The contractor will quote one single rate below/above (HSR+CP) for all items covered under all chapter of HSR of civil work.
2. The contractor will quote also apart from above on single rate below/above (HSR+CP) for items covered under chapter no. 28 & 30 of HSR for Public Health work.
3. The contractor will quote also apart from above on single rate below/above (HSR+CP) for items covered under chapter no. 31 of HSR for Electrical work.
4. Rate of any item not covered in HSR or in DNIT will be finalized as per the prevailing market rates as NS item.
5. Removal of vegetation/small trees/their roots etc. from walls/roofs/parapets etc. is included in the above relevant rates. Nothing extra shall be paid on this account.

DNIT for work “Providing and fixing 5” long G.I. fasteners in Red Agra Stone lining of various Faculties (Law, IMSAR, New Arts Faculty) in MDU, Rohtak”

App. Amt. Rs. 6.70 lac

Earnest money: Rs. 13,400/-
2,000/-

Time Limit 3 months

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|------------|--|---|---------|
| 1/14.59 | 272 sqm | Fine dressed and rubbed red sand stone (from Agra) 25mm to 30mm thick on wall facing (lining) on wall, pillars, skirting, dado and riser of step laid in any pattern as specified on 12mm thick cement coarse sand mortar 1:3 with neat cement with an admixture of pigment to match the shade of stone including labour for fixing cramps, dowels and pins etc. | 190.70 (Rs. One hundred ninety and paisa seventy only) | Per sqm |
| 2/N.S. | 19728 nos. | Providing and fixing 125mm long and 12mm dia G.I. fasteners (Hilty make) in Red Agra Stone fixed on walls including cost of drilling holes, scaffolding and refilling of joints of stone if required as per entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Each |

- NOTE: 1. Contractor will quote single percentage rate below/above on (HSR+CP) on all chapters of HSR.
2. Any damage to the surface will be made good to the original surface.