

# MAHARSHI DAYANAND UNIVERSITY ROHTAK

## NOTICE INVITING TENDER

Sealed tenders on percentage basis are invited on behalf of the Registrar, MDU, Rohtak from contractors/societies / agencies on approved list of Haryana PWD B&R / P.H. Br., MES, CPWD, autonomous bodies and other State / Centre Govt. undertakings. The tender forms will be issued to the contractors / societies / agencies up to the date of opening of tenders as mentioned against work by 12:00 Noon and will be received upto 2:00 P.M. in the office of the Registrar and opened at 3:00 P.M. on the same day in the Committee Room of Vice-Chancellor office in the presence of the tenderers or their authorized representatives, who may like to be present at that time. **The tender documents may be obtained from the office of the undersigned and the same be deposited in the office of the Registrar by the due date.**

Sr. No.	Name of work	App. Amt. (Rs.)	Earnest Money (Rs.)		Cost of tender form (Rs.)	Date of opening of tender	Time limit
			Society	Contractor			
1.	Raising of Boundary Wall of Girls Hostel Complex in MDU, Rohtak	17,00,000/-	1,7000/-	3,4000/-	5,000/-	17.01.2013	04 months
2.	Renovation of Entrance Lobby (including E.I.) at UILMS, Gurgaon	11,50,000/-	11,500/-	23,000/-	1,000/-	17.01.2013	02 months
3.	Construction / laying of new sewer line in the campus of UILMS, Gurgaon	5,95,000/-	5,950/-	11,900/-	1,000/-	17.01.2013	01 month

### CONDITIONS:-

1. Complete NIT / DNIT (Detailed Notice Inviting Tender) alongwith eligibility criteria/terms & conditions and changes if any can be seen in the office of undersigned on any working day during office hours (9:00 AM to 5:00 PM) and on University Website – [www.mdurohtak.ac.in](http://www.mdurohtak.ac.in)
2. The tenderer will keep in touch with the University Web site for any change in the NIT / DNIT till the last date/revised last date of sale of tender and incorporate such changes in NIT / DNIT and the tender bids.
3. At the time of purchase of tender documents, the contractors should submit the following documents:-
  - (a) Proof of enlistment.
  - (b) Copy of PAN card.
  - (c) Copy of latest income tax return.
  - (d) Successfully work done certificates of similar nature of works during last 5 years including the running financial year as under:-
    - One certificate of 80% of the estimated cost of this tender.
    - Or
    - Two certificates of 60% of the estimated cost of this tender
    - Or
    - Three certificates of 40% of the estimated cost of this tender

All the above certificates in paras 3(a) to 3(d) above will be self attested and stamped with the stamp of the firm.

4. In case tendering day happens to be a holiday, the tenders will be received / opened on next working day at the same time.
5. Validity of tender will be 90 days.
6. Earnest money is to be deposited at the time of purchase of the tender. It should be in the shape of Demand Draft or Deposit at Call in favour of the Executive Engineer, MDU, Rohtak payable at Rohtak.
7. Contractors shall quote single percentage of rate below/above/at par on (HSR+C.P.) on all chapters. N.S. item rates are to be quoted separately. The tender, without the rates of N.S. items, if any, in DNIT, will be rejected.
8. Conditional tender is liable to be rejected.
9. Any work, here tendered, may be withdrawn from further processing at any stage at the discretion of the competent authority without assigning any reason.
10. Engineer-in-Charge is competent to increase / decrease the quantity of work. In case of decrease of quantity, the contractor shall have no claim to any payment or compensation whatsoever on account of any profit or advantage which he might have derived from the execution of the work in full.
11. Nothing extra whatsoever shall be paid on account of losses, damages done by rains or any other natural calamity.
12. The tender is liable to be rejected if the tender is found in variance of the above conditions or the conditions of the DNIT.
13. The University reserves the right to accept or reject or negotiate any of the tender or conditions/items without assigning any reason.
14. Plumbing and E.I. work shall be got done through license holder agencies for the works involving PH / E.I.
15. The agencies shall paste the cello tape on the rates quoted by them.
16. Tender by post / telegraphic/courier shall out rightly be rejected.
17. Exemption of tender fee or earnest money or security will not be permitted in any case.

Executive Engineer

Endst. No. EE/ 2012 / 8954-8989

Dated: 28.12.2012

A copy of the above is forwarded to the following for information and necessary action:-

1. Superintending Engineer, PWD B&R Circles, Rohtak
2. Technical Advisor to VC, MDU, Rohtak
3. Executive Engineer(C-II), MDU, Rohtak
4. Executive Engineer, PWD B&R (Medical College), Rohtak / KUK / HAU. Hisar / GJU, Hisar / CDLU, Sirsa / BPS Women University, Khanpur/ DBSCRU, Murthal
5. Secretary to Vice-Chancellor (for kind information of the Vice-Chancellor), M. D. University, Rohtak
6. P.A. to Registrar (for kind information of Registrar), MDU, Rohtak
7. SDE(C-I, II, III) / SDE (E-I) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
8. Divisional Accountant / H.D.M., Engineering Cell, MDU, Rohtak
9. Notice Board
10. Contractor/Agency/Society:\_\_\_\_\_

Executive Engineer

## DETAILED NOTICE INVITING TENDER

**Name the work “Raising of Boundary wall of Girls Hostel Complex in M.D.U, Rohtak”**

**App. Amt. Rs. 17,00,000/-**  
**Earnest Money Rs. 34,000/- / Rs. 17,000/-**  
**Time Limit: 4 Months**

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/11.9	198 cum	1 <sup>st</sup> class brick work laid in cement sand mortar 1:4 in first storey upto 4 metres above plinth level.	@ Rs.445.60 (Rs . Four hundred forty five and paisa sixty only)	Per cum
2/10.59	3.87 cum	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in first storey upto 4 metres above plinth level.	@ Rs. 621.85 (Rs. Six hundred twenty one and paisa eighty five only)	Per cum
3/9.11	34 sqm	Centring and shuttering for corbel, parapets, fascias and other similar items, including edges	@ Rs. 39.60 (Rs. Thirty nine and paisa sixty only)	Per sqm
4/15.10	1166.51 sqm	15 mm thick cement plaster 1:4 on the rough side of single or half brick wall	@ Rs. 15.65 (RS. Fifteen & paisa sixty five only)	Per sqm
5/15.60	862.49 sqm	Cement pointing 1:2 deep variety on brick and tile work	@ Rs. 9.90 (Rs. Nine and paisa ninety only)	Per sqm
6/14.9	301.55 sqm	Conglomerate floor 40 mm thick cement concrete topping 1:2:4	@ Rs. 31.50 (Rs. Thirty one and paisa fifty only)	Per sqm
7/18.12	18.43 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guards, iron doors open-able or fixed stair case or parapet or any other type of railing, gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1040.35 (Rs. One thousand forty and paisa thirty five only)	Per qtl
8/16.25	4716.88 sqm	Applying priming coat with cement primer in all shades on newly plastered or concrete exterior surfaces.	@ Rs. 4.15 (Rs. Four and paisa fifteen only)	Per sqm
9/16.79 (b)	4716.88 sqm	Providing two coats of exterior acrylic emulsion paint. b) 1 <sup>st</sup> quality.	@ Rs. 48.75 (Rs. Forty eight and paisa seventy five only)	Per Sqm

Contnd. Next Page

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
10/10.86+ 10.95(a)	9.92 cum	Cement concrete 1:1½:3 with stone aggregate 20 mm nominal size for reinforced concrete work for walls exceeding 20 cm thickness (straight and curved) beams, girders, stairs, columns, (straight or rectangular) battens and lintels etc. excluding steel reinforcement but including centering and shuttering, laid in position, complete in all respects. (a) extra over item nos. 10.79 to 10.94, if 1: 1½:3 mix is used instead of 1:2:4	@ Rs. 1188.75 (Rs. One thousand one hundred eighty eight & paisa seventy five)	Per cum
11/18.22	14.88 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. nine hundred seventeen and paisa five only)	Per qtl.
12/8.6 (e)	2.62 cum	Dismantling Concrete (e) Reinforced cement concrete with cleaning and straightening and cutting of bars if required.	@ Rs. 108.05 (Rs. One hundred and paisa five only)	Per cum
13/N.S.	244 Nos.	Cutting existing angle iron complete to the entire satisfaction of Engineer-in-charge.	Rates to be quoted by the Contractor	Each
14/N.S.	701 mtrs.	Removing barbed wires four rows and making the rolls and return to store complete to the entire satisfaction of Engineer-in-charge.	Rates to be quoted by the Contractor	Per mtr.
15/N.S.	2621 sqm	Providing 1st quality Apex one coat complete to the entire satisfaction of Engineer-in-charge.	Rates to be quoted by the Contractor	Per Sqm
16/N.S.	838 mtrs.	Providing and Fixing Concertina coil fencing of 610 mm (having 50 nos. round per 6 mtr. length) upto 3 mtr. height of wall with existing angle iron 'Y' shaped placed 2.4 mtr or 3 mtr apart complete to the entire satisfaction of Engineer-in-charge.	Rates to be quoted by the Contractor	Per mtr.
17/N.S.	585 mtrs.	Removing and re-fixing Concertina coil fencing complete to the entire satisfaction of Engineer-in-charge.	Rates to be quoted by the Contractor	Per mtr.
18/N.S.	1100 kg	Credit for M.S. iron angles (removed from the boundary wall).	Rates to be quoted by the Contractor	Per kg

DETAILED NOTICE INVITING TENDER

**Name of work** “Renovation of Entrance Lobby (including E.I.) at ILMS, Gurgaon”

App. Amt. Rs. 11,50,000/-

Earnest Money Rs. 23,000/- / Rs. 11,500/-

Time Limit: 02 months

Sr. No.	Qty.	Description	Rate (Rs.)	Unit
1/6.6	30.00 cum	Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches , stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction , including disposal of all surplus soil, as directed with in a leadoff 30 meters	@ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only)	Per % cum
2/8.5(b)	06 cum	(D) dismantling brick work tile masonry or tile lining and tile terracing (b) in cement	@ Rs. 35.60 (Rs. Thirty five & paisa sixty only)	Per cum
3/10.39	05 cum	Cement concrete 1:4:8 with stone aggregate 40 mm nominal size in foundation and plinth.	@ Rs. 403.10 (Rs. four hundred three and paisa ten only)	Per cum
4/10.82 + 10.95(a)	3.00 cum	Cement concrete 1:1½:3 instead of cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in slabs with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement, but including centering and shuttering, laid in position, complete in all respects. (i) 1 <sup>st</sup> storey	@ Rs. 1,084.80 (Rs. one thousand eighty four and paisa eighty only)	Per cum
	3.00 cum	(ii) 2 <sup>nd</sup> storey	@ Rs. 1,092.10 (Rs. One thousand ninety two and paisa ten only)	Per cum

Contd...P/2....

Sr. No.	Qty.	Description	Rate (Rs.)	Unit
5/10.86 + 10.95(a)	3.00 cum	Cement concrete 1:1½ :3 with stone aggregate 20 mm nominal size for reinforced concrete work for walls exceeding 20 cm thickness (straight and curved) beams, girders, stairs, columns, (straight or rectangular) battens and lintels etc. excluding steel reinforcement but including centering and shuttering , laid in position, complete in all respects. (a) extra over item nos. 10.79 to 10.94, if 1: 1½:3 mix is used instead of 1:2:4 (i) 1 <sup>st</sup> storey	@ Rs. 1188.75 (Rs. One thousand one hundred eighty eight & paisa seventy five)	Per cum
	3.00 cum	(ii) 2 <sup>nd</sup> storey	@ Rs. 1,196.05 (Rs. One thousand one hundred ninety six and paisa five only)	Per cum
6/10.90 + 10.95(a)	05 cum	Cement concrete 1:1½:3 instead of cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in footings, strips, foundations, beams, rafts, pedestals and approach slabs of bridges etc., excluding steel reinforcement but including centering and shuttering, laid in position, complete in all respects, (for work upto 1.5 metres below ground level.)	@ Rs.774/- (Rs. seven hundred seventy four only)	Per cum
7/11.2	05 cum	First class brick work laid in cement sand mortar 1:6 in foundation and plinth	@ Rs. 393.45 (Rs. three hundred ninety three & paisa forty five only)	Per cum
8/11.7	20 cum	First class brick work laid in cement sand mortar 1:6 in first storey upto 4 meters above plinth level 1 <sup>st</sup> storey	@ Rs. 414.45 (Rs. Four hundred fourteen & paisa forty five only)	Per cum
	20 cum	2 <sup>nd</sup> storey	@ Rs. 422.70 (Rs. Four hundred twenty two & paisa seventy only)	Per cum

Sr. No.	Qty.	Description	Rate (Rs.)	Unit
9/11.48(a)	18 cum	(a) 11.43 cm thick brick wall laid in cement sand mortar 1:4 in superstructure 1 <sup>st</sup> storey	@ Rs. 55.10 (Rs. Fifty five & paisa ten only)	Per sqm
	18 cum	2 <sup>nd</sup> storey	@ Rs. 56.05 (Rs. Fifty six and paisa five only)	Per cum
10/13.13	42 sqm	Terracing consisting of tiles 22.86 cm x 11.43 cm x 3.81 cm laid over 87.50 mm mud filling on a layer of 25 mm mud plaster and another layer of mud mortar for laying the tiles, including two coats of bitumen laid hot at 1.65 Kg per sqm on top of RCC slab including 1:3 and top surface to be left clean etc.	@ Rs. 52.95 (Rs. fifty two and paisa ninety five only)	Per sqm
11/13.91	42 sqm	Providing and fixing false ceiling with 12mm thick Gympsum Board fixed on M.S. steel runners frame including cost of screws angles, cleats, rawel pugs, with taping, filling with Gypsum compound and applying priming coat etc. complete in all respects.	@ Rs. 600/- (Rs. six hundred only)	Per sqm
12/15.7	39 sqm	12 mm thick cement plaster 1:6 1 <sup>st</sup> storey	@ Rs. 10.65 (Rs. Ten & paisa sixty five only)	Per sqm
	39 sqm	2 <sup>nd</sup> storey	@ Rs. 10.83 (Rs. Ten and paisa eighty three only)	Per sqm
13/15.12	39 sqm	15 mm thick cement plaster 1:6 on the rough side of single or half brick wall. 1 <sup>st</sup> storey	@ Rs. 13.10 (Rs. Thirteen & paisa ten only)	Per sqm
	39 sqm	2 <sup>nd</sup> storey	@ Rs. 13.28 (Rs. Thirteen and paisa twenty eighty only)	Per sqm



Sr. No.	Qty.	Description	Rate (Rs.)	Unit
14/17.95 + Note 17.96(ii)	750 kg.	Providing and fixing aluminum work for doors, windows, ventilator and partitions with extruded built up standard tubular sections/appropriate Z section and other section of approved make conforming to IS:733 and IS:1285 fixed with rawl plugs and screws or with fixing clips or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom, and sides with required neoprene felt etc aluminum sections shall be smooth, rust free straight mitered and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing/paneling C.P. brass/stainless steel screws, all complete. Fixed portion (Anodized aluminum transparent or dyed to required shade according to IS : 1868, minimum anodic coating of grade AC 15)	@ Rs. 262.30 (Rs. Two hundred sixty two and paise thirty only)	Per kg.
15/17.98(b)	10.22 sqm	Providing and fixing glazing in aluminum door, windows, ventilator shutter and partitions etc. with PVC /neoprene gasket etc complete (cost of aluminum snap beading shall be paid in basic items) (b) with glass panes of 5.00 mm thickness	@ Rs. 700.00 (Rs. Seven hundred only)	Per sqm
16/18.22	30 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works, where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. Nine hundred seventeen & paise five only)	Per qtl.
17/NS	35 sqm	Laying and fixing Granite Stone in all shades 15mm to 18mm thick in flooring, laid in any pattern as specified over base of 20mm thick cement coarse sand mortar 1:3 and jointed with white cement slurry mixed with pigment to match the shade of Granite Stone as per entire satisfaction of Engineer-in-Charge (excluding the cost of Granite Stone)	Rate to be quoted by the contractor	Per sqm

Sr. No.	Qty.	Description	Rate (Rs.)	Unit
18/NS	155 sqm	Painting two coats with ready-mixed exterior paint in all shades on newlyt plastered or concrete surface on walls as per entire satisfaction of Engineer-in-Charge. (Ashian-APEX, Berger weather coat)	Rate to be quoted by the contractor	Per sqm
19/NS	4.50 rmt.	Providing and fixing stainless steel railing of 304 grade, 90 cm high with 50mm dia 14G round pipe for hand rail and bluster of 50mm dia 16G round pipe including cross stailless steel bar of 3 nos. 12mm dia and round base and top plate of 4"x5/8" / 3"x5/8" including buffing compelte in all respect as per entire satisfaction of Engineer in charge. (Make: Vista/Ozone)	Rate to be quoted by the contractor	Per rmt.
20/NS	30 sqm	Providing and fixing of 1mm thick laminate sunmica (Greenlam/Merino) on 12mm thick BWR ply (Century/Duro/Greenply). The ply shall be fixed on a necessary G.I. framework(Make-Gypsteel / India Gypsum or Gabson) comprixsing of 48mm studs ( 0.55mm thick having one flange of 34mm and another flange of 36mm made of G.I. steel) placed at 600mm centre to centre both way (maximum or less wherever required) in 50mm floor and ceiling channel(0.55mm thick having equal flanges of 32mm made of G.I. steel) in desirable profile (sStraight or Curved). The shade & design shall be as per approval of Architect/Engineer-in-Charge.	Rate to be quoted by the contractor	Per sqm
21/NS	150 sqm	Supply and applying snow décor amber dholpur synthetic stone like finish made of pure acrylic emulsion reinforced with marble powder and silica sand having antibacterial and antifugal additives with trowel to a thickness of 2-3mm on plastered surface complete in all respects as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per sqm
22/NS	4450 sq.in	ILMS logo as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per sq. in.
23/NS	04 nos.	Removing old aluminium door and refixing as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Each

Sr. No.	Qty.	Description	Rate (Rs.)	Unit
24/NS	55 sqm	Providing and fixing UniStone UniBrick cladding with the specification of size 101mm x 304mm/101mm x 204mm Riverdale fixed onwall with Unistone Ultimate tile adhesive in desired pattern at all height and levels complete in all respect with the entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per sqm

“Renovation of Entrance Lobby at ILMS, Gurgaon—E.I.”

Sr. No.	Qty.	Description	Rate (Rs.)	Unit
1/31.36		Wiring in 1.5 sqmm PVC insulated copper conductor cable in 1.60 mm thick conduit pipe.		
	02 nos.	(i) fan point (b) medium point	@ Rs. 524.00 (Rs. Five hundred twenty only)	Each
	02 nos.	(ii) light point (b) medium point	@ Rs. 433.00 (Rs. Four hundred thirty three only)	Each
	01 nos.	(c) long point	@ Rs. 639.00 (Rs. Six hundred thirty nine only)	Each
	02 nos.	(iii) Twin control light point with 2 way, 5 3ay, 5 amp. Single pole switch. (b) medium point	@ Rs. 486/- (Rs. Four hundred eighty six only)	Each
	01 no.	(c) long point	@ Rs. 726/- (Rs. Seven hundred twenty six only)	Each
	01 no.	viii) 3-pin 15 amp. Plug point with 4 sqmm PVC insulated copper conductor cable including earthing the 3 <sup>rd</sup> pin etc. (c) Long point	@ Rs. 970/- (Rs. nine hundred seventy only)	Each

DETAILED NOTICE INVITING TENDER

Name the work “Construction/laying of new Sewer line in the campus of UILMS, Gurgaon.

App. Amt. Rs. 5,95,000/-  
Earnest Money Rs. 5,950/- / 11,900/-  
Time Limit: 01 month

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/6.10 (a)	266.61 cum	Excavation of trenches in streets, lanes or in open areas for storm sewer, sewers running by gravity and manholes to full depths as shown in drawings including shoring, timbering of poling boards, frame system type, dressing to correct sections and dimensions, according to templates and levels, dewatering, provision for diversion of traffic, cutting trees and bushes etc night signals, profiles, pegs, sight rails, bonding rods crossing over trenches for access to the houses, watching , fencing etc. fixing and maintenance of caution boards, refilling of trenches, watering of refill, in 15 cm layers, ramming and restoration of unmetalled or unpaved surface to original site of work upto a lead of 1 KM in ordinary soil. (a) for depths of excavation not exceeding 3 meters below ground level	@ Rs. 1189.00 (Rs one thousand one hundred eighty nine only)	P.100 cum
2/10.39	40.92 cum	Cement concrete 1:4:8 with stone aggregate 40 mm nominal size in foundation and plinth.	@ Rs. 403.10 (Rs. four hundred three and paisa ten only)	Per cum
3/29.95 (d)	293.83 mtr	Providing, salt glazed stone ware pipes grade ‘A’ in standard length of 600mm each pipe marked with IS:651 and their lowering, cutting, jopinting and testing as described in HSR 29.38, 29.39, 29.40 including the cost of jointing materials as well as carriage, loading, unloading, stacking, handling, re-handling etc. complete in all respects to the satisfaction to the Engineer-in-Charge. (d) 250mm i/d	@ Rs. 386/- (Rs. three hundred eighty six only)	Per mtr.

Contd....2...

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
4/10.41	58.93 cum	Cement concrete 1:2:4 with stone aggregate 20 mm nominal size in foundation and plinth	@ Rs. 615.60 (Rs. Six hundred fifteen & paisa sixty only)	Per cum
5/29.84 (c)	20 nos.	Constructing brick masonry inspection chamber size as given below upto 0.60 metre average depth in cement mortar 1:5 lime concrete with 40 percent lime mortar 2:3 in foundation cement concrete 1:2;4 benching 12 mm thick cement plaster 1:2 with a floating coat of 1 mm thick of neat cement RCC1:2:4 slab 100 mm thick/C.C. topping, 50 mm thick with 455 mm x 455 mm/455mmx610 mm inside light duty C.I. inspection chamber cover and frame weight as per I.S. specification painted with 3 coats of black bitumastic superior paint complete as per standard design. (c) size 600 mm x 900 mm inside (with 455 mm x 455 mm cover and frame light duty single seal weighing 20 kg with RCC slab)	@ Rs. 690.00 (Rs. Six hundred ninety only)	Each
6/29.85 (c)	12 mtr	Extra for every 0.30 metre depth of inspection chamber (c) 600 mm 900 mm	@ Rs. 139.00 (Rs. One hundred thirty nine only)	Per 0.30 metre depth
7/24.37	72.46 sqm	Dismantling of Road including soling and wearing coat, screening and stacking of old serviceable material, complete in all respect	@ Rs. 296.70 (Rs. two hundred ninety six and paisa seventy only)	Per 100 sqm
8/10.132	11.04 cum	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in pavement, roads, taxi-tracks and run ways, laid to required slope and camber, including consolidation, finishing and tamping complete	@ Rs. 642.40 (Rs. six hundred forty two and paisa forty only)	Per cum