

**MAHARSHI DAYANAND UNIVERSITY ROHTAK**

**NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar, MDU, Rohtak for the below noted work from the societies/contractors on approved list of Haryana PWD B&R / P.H. Br., MES/CPWD autonomous bodies and other State/Centre Govt. undertakings on plain paper on dated 03.10.2012 at 2.00 PM. Quotations will be opened at 3.00 PM on the same date in the presence of quotationers or their representative who may like to be present at that time.

Sr. No.	Description	App. Amt. (Rs.)	Time Limit
1.	DNIQ for Raising of boundary wall and Construction of CC flooring in Gas Godown in MDU, Rohtak	80,000/-	01 month

NOTE: The DNIT can be seen in the office of undersigned on any working day during office hours (9.00AM to 5.00 PM).

Executive Engineer

Endst. No. EE/ 2012 / 6984-7002

Dated: 27.09.2012

A copy of the above is forwarded to the following for information and necessary action: -

1. Technical Advisor to VC, MDU, Rohtak
2. P.A. to Registrar (for kind information of Registrar), MDU, Rohtak
3. SDE(C-I, II, III) / SDE (E-I, II) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
4. Asstt. Registrar(Engg. Cell) / H.D.M., Engineering Cell, MDU, Rohtak
5. Notice Board – Registrar office & Executive Engineer office.
6. Contractor/Agency/Society: \_\_\_\_\_

Executive Engineer

## DETAILED NOTICE INVITING TENDER

**Name of work “Raising of boundary wall and constriction of CC flooring in Gas Godown in MDU, Rohtak”**

**App. Amt. Rs. 80,000/-**

**Time Limit: 01 month**

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/11.8	13 cum	First class brick work laid in cement sand mortar 1:5 in first storey upto 4 metres above plinth level.	@ Rs. 428.60 (Rs. four hundred twenty eight and paise sixty only)	Per cum
2/15.6	56 sqm	12mm thick cement plaster 1:4	@ Rs. 11.60 (Re. eleven and paise sixty only)	Per sqm
3/15.11	56 sqm	15mm thick cement plaster :5 on the rough side of single or half brick wall.	@ Rs. 14.25 (Rs. fourteen and paise twenty five only)	Per sqm
4/6.2(b)	06 cum	Earth work excavation in ordinary soil exclusive of compensation of earth: (a) earth work undressed with a combined lead upto 15 metres including breaking of clods.	@ Rs.586.60 ( Rs. five hundred eighty six and paise sixty only)	Per 100 cum
5/10.26	09 cum	Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth	@ Rs. 300.20 (Rs. Three hundred & paise twenty only)	Per cum
6/14.10	84 sqm	Conglomerate floor 50 mm thick cement concrete topping 1:2:4	@ Rs. 37.60 (Rs. Thirty seven and paise sixty only)	Per sqm
7/14.9	13 sqm	Conglomerate floor 40 mm thick cement concrete topping 1:2:4	@ Rs. 31.50 (Rs. Thirty one & paise fifty only)	Per sqm
8/14.79	21 rmt.	Providing and fixing glass strips, 4mm thick in floors. (a) 40mm wide	@ Rs. 3.50 (Rs. Three and paise fifty only)	Per mtr.
9/16.48	112 sqm	White washing three coat	@ Rs. 1.25 ( Rs. One and paise twenty five only)	Per sqm