

**MAHARSHI DAYANAND UNIVERSITY ROHTAK
SHORT TERM NOTICE INVITING TENDER**

Sealed tenders on percentage basis are invited on behalf of the Registrar, MDU, Rohtak from Co-Operative L/C Societies, contractors on approved list of Haryana PWD B&R / P.H. Br., MES / CPWD, autonomous bodies and other State / Centre Govt. undertakings. The tenders forms will be issued to the societies up to the date of opening of tenders as mentioned against each work by 1:00 P.M. and will be received upto 3:00 P.M. and opened at 3:30 P.M. on the same day in the office of the Registrar. If the received tenders are less than three, then the tenders will be issued to the contractors / Societies (both) by 1:00 P.M. on the next date as mentioned against each and will be received upto 3:00 P.M. and opened at 3:30 P.M. on the same date in the presence of the tenderers or their authorized representatives, who may like to be present at that time. **The tender documents may be obtained from the office of the Registrar and the same be deposited there by the due date.**

Sr. no.	Name of work	App. Amt. (Rs. in lac)	Earnest money Society/ Contractor(Rs.)	Cost of tender form (Rs.)	Date of opening of tender Society/ Contractor	Time limit
1.	Repair of Sewer line in MDU Campus	10.00	<u>2,000/-</u> 20,000/-	1,000/-	<u>03.01.2011</u> 04.01.2011	01 month
2.	Construction of Workshop near Shopping Complex	5.50	<u>2,000/-</u> 11,000/-	1,000/-	<u>03.01.2011</u> 04.01.2011	03 months
3.	Construction of Screen House for Dept. of Environment Science	3.38	<u>2,000/-</u> 6,760/-	500/-	<u>03.01.2011</u> 04.01.2011	02 months

CONDITIONS:-

- In case tendering day happens to be a holiday, the tenders will be received / opened on next working day at the same time and venue.
- Earnest money is to be deposited at the time of purchase of tender. It should be in the shape of demand draft/deposit at call receipt of any schedule Bank, pledged to the Executive Engineer, MDU, Rohtak payable at Rohtak.
- Contractors shall quote single percentage of rate below/above on(HSR+C.P.) on all chapters. N.S. item rates are to be quoted separately. The tender without the rates of N.S. items, if any in DNIT, the tender will be rejected.
- The contractors should bring their proof of enlistment with copy of PAN card and one successfully work done certificate of approximate same amount during last one year.
- Tender having conditional rebates shall be considered invalid and shall be out rightly rejected
- Any work, here tendered, may be withdrawn from further processing at any stage at the discretion of the competent authority without assigning any reason.

Contd.....P/2.....

7. Nothing extra whatsoever shall be paid on account of losses, damages done by rains or any other natural calamity.
8. Plumbing and E.I. work shall be got done through license holder agencies for works involving PH / E.I.
9. The tender will be out rightly rejected if the tender is found in variance of the above conditions or the conditions of the DNIT.
10. The contractors / agencies shall paste the cello tape on the rates quoted by them.
11. Notice inviting tender can be seen at web site www.mdurohtak.com

Endst. No. EE/ 2010 / 5950-5990

Dated: 20.12.2010

Executive Engineer

A copy of the above is forwarded to the following for information and necessary action:-

1. Superintending Engineer, PWD B&R Circles, Rohtak
2. Executive Engineer, PWD B&R (Medical College), Rohtak
3. Executive Engineer, KUK / HAU. Hisar / GJU, Hisar / CDLU, Sirsa
4. Secretary to Vice-Chancellor (for kind information of worthy Vice-Chancellor), M. D. University, Rohtak
5. P.A. to Registrar (for kind information of Registrar), MDU, Rohtak
6. SDE(C-I, II, III) / SDE (E-I, II) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
7. Divisional Accountant / H.D.M., Engineering Cell, MDU, Rohtak
8. Notice Board
9. Contractor/Agency/Society:_____

Executive Engineer

Detail for the work “Repair of sewer line in MDU Campus, Rohtak”

App. Amt. Rs. 10,00,000/-

Earnest Money Rs. 20,000/-

Rs. 2,000/-

Time Limit: 01 Month

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/ 10.39 + Note V (e) ii	5.60 cum	Cement concrete 1:4:8 with stone aggregate 40 mm nominal size in foundation and plinth	@ Rs. 408.20 (Rs. four hundred eight and paise twenty only)	Per cum
2/ 10.90+ 10.95(a) + note V (e)1	3.50 cum	Cement concrete 1:½:3 instead of cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in footings, strips, foundations, beams, rafts, pedestals and approach slabs of bridges etc., excluding steel reinforcement but including centering and shuttering, laid in position, complete in all respects, (for work upto 1.5 metres below ground level.)	@ Rs.779.10 (Rs. seven hundred seventy nine and paise ten only)	Per cum
3/10.87 + 10.95(a)	15.00 cum	Cement concrete 1:½:3 instead of cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work for walls (10 cm to 20 cm thickness) straight and curved excluding steel reinforcement but including centering and shuttering, laid in position, complete in all respects.	@ Rs. 1,486.90 (Rs. one thousand four hundred eighty six and paise ninety only)	Per cum

Contd....P/2.....

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
4/10.82 + 10.95(a)	1.36 cum	Cement concrete 1:1½:3 instead of cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in slabs with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement, but including centering and shuttering, laid in position, complete in all respects.	@ Rs. 1,084.80 (Rs. one thousand eighty four and paisa eighty only)	Per cum
5/18.22	24.00 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. Nine hundred seventeen & paisa five only)	Per qtl.
6/29.95(c)	5.00 cum	Providing, lowering laying, cutting (cut surface to be uniformly finished), jointing with rubber rings marked with IS:5382 and testing of Spigot and socketted RCC NP3 marked with IS: 458-1988 and specials into trenches for all depths including carriage, loading, unloading staking, handling, re-handling etc. complete in all respects to the satisfaction to the Engineer-in-Charge. (a) 450mm i/d	@ Rs. 1,343/- (Rs. one thousand three hundred forty three only)	Per cum
7/10.41	1.00 cum	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in foundation and plinth.	@ Rs. 615.60 (Rs. six hundred fifteen and paisa sixty only)	Per cum
8/N.S.	01 no.	Dismantling of manhole, remove the material of 100 mtr. distance entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Each
9/N.S.	01 no.	Connection of RCC pipe in manhole and screen chamber and cutting holes as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Each

Contd....P/3.....

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
10/N.S.	1250 cum	Earth work in excavation of all kinds of soils with dewatering to lower down the water table upto the required depth and refilling as per entire satisfaction of Engineer-in-Charge. (Depth may be 22' to 25')	Rate to be quoted by the contractor	Per cum
11/N.S.	Job work	Pumping out the sewer water of sewer line at 3 rd manhole by plugging the line alongwith labour and material as per site requirement and entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Per week (7 days)
12/11.4	3.00 cum	First class brick work laid in cement sand mortar 1:4 in foundation with plinth	@ Rs. 424.60 (Rs. four hundred twenty four and paisa sixty only)	Per cum

Detail for the work “Construction of Workshop for maintenance works near Shopping Complex in MDU, Rohtak”

App. Amt. Rs. 5,50,000/-

Earnest House Rs. 2,000.00

Rs. 11,000.00

Time Limit: 3 Months

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/6.6	23 cum	Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches , stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction , including disposal of all surplus soil, as directed with in a leadoff 30 meters	@ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only)	Per % cum
2/10.26	06 cum	Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth	@ Rs. 300.20 (Rs. Three hundred & paisa twenty only)	Per cum
3/11.4	11 cum	1 st class brick work laid in cement sand mortar 1:4 in foundation and plinth.	@ Rs. 424.60 (Rs. Four hundred and paisa twenty four and paisa sixty only)	Per cum
4/11.9	35 cum	1 st class brick work laid in cement sand mortar 1:4 in first storey upto 4 metres above plinth level.	@ Rs. 445.60 (Rs. Four hundred forty five and paisa sixty only)	Per sqm
5/10.115 – note	9.34 sqm	Damp proof course 25 mm thick of cement concrete 1:2:4 using stone aggregate 20mm nominal size with 2 coats of bitumen 20/30 penetration at 1.65 kg. per sqm laid hot and sanded	@ Rs. 17.95 (Rs. Seventeen and paisa ninety five only)	Per sqm

Contd....P/2.....

-2-

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
6/15.5	15 sqm	12 mm thick cement plaster 1:4	@ Rs. 12.70 (Rs. Twelve & paisa seventy only)	P.sqm
7/15.11	157 sqm	15mm thick cement plaster 1:5 on the rough side of single or half brick wall.	@ Rs. 14.25 (Rs. fourteen and paisa twenty five only)	Per sqm
8/15.60	188 sqm	Cement pointing 1:2 deep variety on brick and tile work	@ Rs. 9.90 (Rs. Nine and paisa ninety only)	Per sqm
9/18.12	11.00 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors open-able or fixed stair case or parapet or any other type of railing , gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1040.35 (Rs. One thousand forty & paisa thirty five only)	Per qtl
10/18.16	5.80 sqm	Providing & fixing G.I. sheet 0.80 mm thick gauze doors with 40mm x 40mm x 6mm angle iron frame with diagonal braces, 3mm thick gusset plates at the junctions, hooks at the top and 25mm dia, pulleys and T-iron 50mm x 50mm x 6mm guides at bottom including locking arrangements with handles and pintles etc. complete.	@ 424.00 (Rs. Four hundred twenty four only)	Per sqm

Contd....P/3.....

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
11/13.18	116 sqm	Corrugated G.I. sheet roofing 0.80 mm thick fixed with galvanized iron "J" or "L" hooks, 10mm dia G.I. limpet and bitumen washers complete, excluding the cost of purlins, rafters and trusses.	@ Rs. 137.40 (Rs. One hundred thirty seven and paisa forty only)	Per sqm
12/6.2(b)	71 cum	Earth work excavation in ordinary soil exclusive of compensation of earth: (b) Earth work undressed with a combined lead upto 15 metres including breaking of clods.	@ Rs.586.60 (Rs. five hundred eighty six and paisa sixty only)	Per 100 cum
13/6.2(i)(c)	71 cum	Earth work excavation in ordinary soil exclusive of compensation of earth:- When overall lead is upto 60 metres: i) Extra for every 7.5 metres additional lead beyond 15 metres, but upto 60 metres by manual mean	@ Rs. 22.65 (Rs. Twenty two and paisa sixty five only)	Per % cum
14/10.48	71 cum	Cement concrete 1:6:12 with brick ballast 40mm nominal size in first storey upto 4 metres above plinth level.	@ Rs. 336.20 (Rs. Three hundred thirty six and paisa twenty only)	Per cum
15/10.132	53 cum	Cement concrete 1:11/2:3 with stone aggregate 20mm nominal size in pavement, roads, taxi-tracks and run ways, laid to required slope and camber, including consolidation, finishing and tamping complete	@ Rs. 642.40 (Rs. six hundred forty two and paisa forty only)	Per cum

Contd....P/4.....

Sr. No./ HSR	Qty.	Description	Rate (Rs.)	Unit
16/10.86 + 10.95(a)	0.57 cum	Cement concrete 1:1½:3 with stone aggregate 20mm nominal size for reinforced concrete work for walls exceeding 20 cm thickness (straight and curved) beams, girders, stairs, columns, (square or rectangular) battens and lintels etc. excluding steel reinforcement but including centering and shuttering, laid in position, complete in all respects. (a) xtra over item nos. 10.79 to 10.94, if 1:1½:3 mix is used instead of 1:2:4	@ Rs. 1,188.75 (Rs. one thousand one hundred eighty eight and paisa seventy five only)	Per cum
17/18.22	1.86 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. Nine hundred seventeen & paisa five only)	Per qtl.
18/14.20	24 sqm	Dry brick –on-edge paving sand grouted over 50mm thick earth and mud plaster	@ Rs. 38.70 (Rs. Thirty eight and paisa seventy only)	Per sqm
19/16.48	98 sqm	White washing three coats	@ Rs. 1.25 (Rs. One & paisa twenty five only)	Per sqm
20/16.9	90 sqm	Applying priming coat with metal primer on new steel or iron work including preparation of surfaces.	@ Rs. 2.95 (Rs. Two and paisa ninety five only)	Per sqm
21/16.3	90 sqm	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	@ Rs. 8.05 (Rs. Eight and paisa five only)	Per sqm

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
22/14.92(a)	21 sqm	Providing and fixing 1 st quality ceramic glazed wall tiles confirming to IS 15622 (thickness to be specified by the manufacturer) of approved make in all colors, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12mm thick bed of cement mortar 12:3 coarse and jointed with grey cement slurry, including pointing in white cement mixed with pigment of matching shades complete. (a) Size of ceramic Glazed tiles 200 x 300 mm	@ Rs. 501.75 (Rs. five hundred one and paisa seventy five only)	Per sqm
23/10.82 + 10.95(a)	1 cum	Cement concrete 1:1½:3 with stone aggregate 20mm nominal size for reinforced concrete work in slabs with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement, but including centering and shuttering, laid in position, complete in all respects.	@ Rs. 1,084.80 (Rs. one thousand eighty four and paisa eighty only)	Per cum
24/16.25	731 sqm	Applying priming coats with cement primer in all shades on newly plastered or concrete exterior surfaces	@ Rs. 4.15 (Rs. Four and paisa fifteen only)	Per sqm
25/16.79(b)	731 sqm	Providing two coats of exterior acrylic emulsion paint. b) 1 st quality.	@ Rs. 48.75 (Rs. forty eight and paisa seventy five only)	Per sqm

Credit for dismantled bricks = 3800 nos. @ 2,800/- per thousand nos.

Detail for the work “Construction of Screen House for Department of Environment Science, MDU, Rohtak”

App. Amt. Rs. 3,38,000/-

Earnest House Rs. 6,760.00

Rs. 2,000.00

Time Limit: 2 Months

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/6.6	15.42 cum	Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches , stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction , including disposal of all surplus soil, as directed with in a leadoff 30 meters	@ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only)	Per 100 cum
2/10.26	7.59 cum	Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth	@ Rs. 300.20 (Rs. Three hundred & paisa twenty only)	Per cum
3/11.2	15 cum	First class brick work laid in cement sand mortar 1:6 in foundation and plinth	@ Rs. 393.45 (Rs. three hundred ninety three & paisa forty five only)	Per cum
4/10.114	7.80 cum	Damp proof course 40 mm thick of cement concrete 1:2:4 using stone aggregate 20 mm nominal size with 2 coats of bitumen 20/30 penetration at 1.65 Kg per sqm laid hot and sanded	@ Rs. 35.05 (Rs. Thirty five & paisa five only)	Per cum
5/11.7	6.30 cum	First class brick work laid in cement sand mortar 1:6 in first storey upto 4 meters above plinth level	@ Rs. 414.45 (Rs. Four hundred fourteen & paisa forty five only)	Per cum
6/11.48(a)	24.87 sqm	(a) 11.43 cm thick brick wall laid in cement sand mortar 1:4 in superstructure	@ Rs. 55.10 (Rs. Fifty five & paisa ten only)	Per sqm

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
7/14.1	59.46 sqm	Base course of floors consisting of 100 mm thick concrete 1:8:16 and 100 mm sand or stone filling	@ Rs. 36.95 (Rs. Thirty six & paisa ninety five only)	Per sqm
8/14.10	59.46 sqm	Conglomerate floor 50 mm thick cement concrete topping 1:2:4	@ Rs. 37.60 (Rs. Thirty seven & paisa sixty only)	Per sqm
9/14.79(b)	114.60 mtr.	Providing and fixing glass strips, 4mm thick in floors. (b) 32mm wide	@ Rs. 3.15 (Rs. Three and paisa fifteen only)	Per mtr.
10/10.81	2.79 cum	Cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in Shelves excluding steel reinforcement, but including centering and shuttering, laid in position, complete in all respects.	@ Rs. 947.70 (Rs. nine hundred forty seven and paisa seventy only)	Per cum
11/18.22	3.49 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. Nine hundred seventeen & paisa five only)	Per qtl.
12/15.12	49.70 sqm	15 mm thick cement plaster 1:6 on the rough side of single or half brick wall	@ Rs. 13.10 (Rs. Thirteen & paisa ten only)	Per sqm
13/15.7	49.70 sqm	12 mm thick cement plaster 1:6	@ Rs. 10.65 (Rs. Ten & paisa sixty five only)	Per sqm

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
14/18.12	20.15 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors open-able or fixed stair case or parapet or any other type of railing , gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1040.35 (Rs. One thousand forty & paisa thirty five only)	Per qtl
15 / 16.9 + 16.3	264.58 sqm	Applying priming coat with metal primer on new steel or iron work including preparation of surfaces. Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	@ Rs. 11/- (Rs. Eleven only)	Per sqm
17/N.S.	1424 sft.	Providing and fixing expended metal steel mess approximately weight 250 gm per sft complete to the entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per sft.
18/N.S.	27.17 cum	S/Filling of tibba sand 15 cm layer including watering, compaction, consolidation and ramming etc under floor complete to the entire satisfaction of Engineer-in-Charge	Rate to be quoted by the contractor	Per cum