

MAHARSHI DAYANAND UNIVERSITY ROHTAK

NOTICE INVITING TENDER

Sealed tenders on percentage basis are invited on behalf of the Registrar, MDU, Rohtak from contractors/agencies on approved list of Haryana PWD B&R / P.H. Br., MES, CPWD, autonomous bodies and other State / Centre Govt. undertakings. The tender forms will be issued to the contractors/agencies up to the date of opening of tender as mentioned against the work by 1:00 P.M. and will be received upto 3:00 P.M. and opened at 4:00 P.M. on the same day in the office of the Registrar in the presence of the tenderers or their authorized representatives, who may like to be present at that time. **The tender documents may be obtained from the office of the Registrar and the same be deposited there by the due date.**

Sr. no.	Name of work	App. Amt. (₹ in lac)	Earnest money (₹)	Cost of tender form (₹)	Date of opening of tender	Time limit
1.	Installation of the fire extinguishers at various places in MDU, Rohtak	7.50	15,000/-	1,000/-	10.02.2011	02 month

CONDITIONS:-

1. In case tendering day happens to be a holiday, the tenders will be received / opened on next working day at the same time and venue.
2. Earnest money is to be deposited at the time of purchase of tender form. It should be in the shape of demand draft/deposit at call receipt of any schedule Bank, pledged to the Executive Engineer, MDU, Rohtak payable at Rohtak.
3. Engineer-in-Charge is competent to increase / decrease the quantity of work.
4. The contractors should bring their proof of enlistment with a copy of PAN card and one successfully work done certificate of the approximate same amount during last one year.
5. Conditional tenders shall be out rightly rejected.
6. Any work, here tendered, may be withdrawn from further processing at any stage at the discretion of the competent authority without assigning any reason.
7. Nothing extra whatsoever shall be paid on account of losses, damages done by rains or any other natural calamity.
8. The tender will be out rightly rejected if the tender is found in variance of the above conditions or the conditions of the DNIT.

9. The contractors / agencies shall paste the cello tape on the rates quoted by them.
10. Notice inviting tender can be seen at web site www.mdurohtak.com

Executive Engineer

Endst. No. EE/ 2011 / 298-332

Dated: 21.01.2011

A copy of the above is forwarded to the following for information and necessary action:-

1. Superintending Engineer, PWD B&R Circle, Rohtak
2. Executive Engineer, PWD B&R (Medical College), Rohtak
3. Executive Engineer, KUK / HAU. Hisar / GJU, Hisar / CDLU, Sirsa
4. PA to Vice-Chancellor (for kind information of Vice-Chancellor), M. D. University, Rohtak
5. P.A. to Registrar (for kind information of Registrar), MDU, Rohtak
6. SDE(C-I, II, III) / SDE (E-I, II) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
7. Divisional Accountant / H.D.M., Engineering Cell, MDU, Rohtak
8. Notice Board
9. Contractor/Agency

Executive Engineer

DNIT for the work “Installation of fire extinguishers at various places in MDU, Rohtak”

App. Amt. ` 7,50,000/-
 Earnest Money ` 15,000/-
 Time Limit: 2 months

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/N.S.	40 nos.	Supply and fixing 2 nos. ABC stored pressure type fire extinguisher capacity 5 kg. each ISI marked IS no. 13849 fixed in 1 no. M.S. box of suitable size made of 16 gauge S.W.G M. S. sheet duly painted by white enamel inside and red paint on outside with 5mm thick glass door in front complete in all respect and entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each
2/N.S.	20 nos.	Supply and fixing 1 no. ABC stored pressure type fire extinguisher capacity 5 kg ISI marked IS No. 13849 fixed in 1 no. M.S. box of suitable size made of 16 gauge S.W.G M.S. sheet dully painted by white enamel inside and red paint on outside with 5mm thick glass door in front complete in all respect and entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each
3/N.S.	06 nos.	Supply and fixing 2 nos. Co2 type fire extinguisher of capacity 4.5 kg. each ISI mark IS no. 2878 with 1 no. M.S. box of suitable size made of 16 S.W.G M.S. sheet duly painted by white enamel inside and red paint on outside with 5mm thick glass door in front complete in all respect and entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each
4/N.S.	10 nos.	Supply and fixing 1 no. Co2 type fire extinguisher of capacity 4.5 kg ISI marked IS No. 2878 with 1 no. M.S. box of suitable size made of 16 gauge S.W.G M.S. sheet dully painted by white enamel inside and red paint on outside with and 5mm thick glass door in front side complete in all respect and entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each

Contd...P/2.....

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
5/N.S.	02 nos.	Supply and fixing of 1 no.Co2 type fire extinguishers capacity 4.5 kg. ISI marked IS 13849 fixed in 1 no. M.S. box suitable size made of 16 gauge S.W.G. M.S. sheet duly painted by white enamel inside and red paint outside with 5mm thick glass door in front complete in all respect and entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each
6/N.S.	20 nos.	Supply and fixing of 1 no. ABC type fire extinguisher cap. 5 kg ISI marked IS-13849 fixed on wall complete but without M.S. box entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each
7/N.S.	05 nos.	Supply and fixing of 1 no. ABC type fire extinguisher cap. 10 kg ISI marked IS-13849 fixed on wall but without M.S. box as per entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each
8/N.S.	40 nos.	Providing and fixing M.S. stand made of 20 mm M.S., pipe with 4 nos. fire buckets of 9 ltrs. capacity each made of G.I. sheet filled with Jumna Sand and duly painted with red paint complete in all respect and entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each
9/N.S.	150 nos.	Refilling of existing ABC type fire extinguisher cylinders of ISI mark of 5 kg capacity with checking, testing and commissioning complete in all respects and entire satisfaction of Engineer in Charge.	Rate to be quoted by the contractor	Each

NOTE : 1. Inspection will be at agency workshop.

2. Testing will be done as per ISI specification.