



MAHARSHI DAYANAND UNIVERSITY ROHTAK

(A State University established under Haryana Act No. 25 of 1975)

NAAC accredited 'A' Grade

NOTICE INVITING TENDER

Sealed tenders on percentage basis are invited on behalf of the Registrar, MDU, Rohtak from contractors/societies / agencies on approved list of PWD, MES, CPWD, autonomous bodies and State / Centre Govt. undertakings. The tender forms will be issued to the contractors / societies agencies / up to the date of opening of tenders as mentioned against work by 12:00 Noon and will be received up to 2:00 P.M. in the office of the Registrar and opened at 3:00 P.M. on the same day in the Committee Room of Vice-Chancellor office in the presence of the tenderers or their authorized representatives, who may like to be present at that time. **The tender documents may be obtained from the office of the undersigned and the same be deposited in the office of the Registrar by the due date.**

| Sr. No. | Name of work | App. Amt. (Rs.) | Earnest Money (Rs.) | | Cost of tender form (Rs.) | Date of opening of tender | Time limit |
|---------|--|-----------------|---------------------|------------|---------------------------|---------------------------|------------|
| | | | Society | Contractor | | | |
| 1. | Construction of 04 nos. Lawn Tennis Courts in the Sports Complex in MDU, Rohtak | 27,18,000/- | 27,180/- | 54,360/- | 5,000/- | 07.01.2014 | 04 months |
| 2. | Construction of one no. Basket Ball court and repair of existing Basket Ball Courts in the Sports complex in MDU, Rohtak | 14,42,000/- | 14,420/- | 28,840/- | 1,000/- | 07.01.2014 | 03 months |
| 3. | Supplying and filling tibia sand after excavation of the existing earth and malba between the boundary wall of Bhagirathi, Krishna girls Hostel in MDU, Rohtak | 14,00,000/- | 14,200/- | 28,000/- | 1,000/- | 07.01.2014 | 02 months |

CONDITIONS:-

1. Complete NIT / DNIT (Detailed Notice Inviting Tender) alongwith eligibility criteria/terms & conditions and changes if any can be seen in the office of undersigned on any working day during office hours (9:00 AM to 5:00 PM) or on University Website – www.mdurohtak.ac.in
2. The tenderer will keep in touch with the University Web site for any change in the NIT / DNIT till the last date/revised last date of sale of tender and incorporate such changes in NIT / DNIT and the tender bids.
3. At the time of purchase of tender documents, the contractors should submit the following documents:-
 - (a) Proof of enlistment.
 - (b) Copy of PAN card.
 - (c) Copy of latest income tax return.

Contd...2....

(d) Successfully work done certificates of civil works during last 5 years (financial year 2008-09 to 2012-13) as under:-

One certificate of 80% of the estimated cost of this tender.

Or

Two certificates of 60% of the estimated cost of this tender

Or

Three certificates of 40% of the estimated cost of this tender

All the above certificates in paras 3(a) to 3(d) above will be self attested with stamp.

4. In case tendering receiving / opening day happens to be a holiday, the tenders will be received / opened on next working day at the same time.
5. Validity of tender will be 90 days.
6. Earnest money is to be deposited at the time of purchase of the tender. It should be in the shape of Demand Draft or Deposit at Call in favour of the Executive Engineer, MDU, Rohtak payable at Rohtak.
7. Contractors shall quote single percentage of rate below/above/at par on (HSR+C.P.) on all chapters. N.S. item rates are to be quoted separately. The tender, without the rates of N.S. items, if any, in DNIT, will be rejected.
8. Conditional tender is liable to be rejected.
9. Any work, here tendered, may be withdrawn from further processing at any stage at the discretion of the competent authority without assigning any reason.
10. Engineer-in-Charge is competent to increase / decrease the quantity of work. In case of decrease of quantity, the contractor shall have no claim to any payment or compensation whatsoever on account of any profit or advantage which he might have derived from the execution of the work in full.
11. Nothing extra whatsoever shall be paid on account of losses, damages done by rains or any other natural calamity.
12. The tender is liable to be rejected if the tender is found in variance of the above conditions or the conditions of the DNIT.
13. The University reserves the right to accept or reject or negotiate any of the tender or conditions/items without assigning any reason.
14. Plumbing and E.I. work shall be got done through license holder agencies for the works involving PH / E.I.
15. The agencies shall paste the cello tape on the rates quoted by them.
16. Tender by post / telegraphic/courier shall out rightly be rejected.
17. Exemption of tender fee or earnest money or security will not be permitted in any case.

Executive Engineer

Endst. No. EE/ 2013 / 6581-6615

Dated: 10.12.2013

A copy of the pre-page is forwarded to the following for information and necessary action:-

1. Superintending Engineer, PWD B&R Circles, Rohtak
2. Technical Advisor to VC, MDU, Rohtak
3. Executive Engineer(C-II), MDU, Rohtak
4. Executive Engineer, PWD B&R (Medical College), Rohtak / KUK / HAU. Hisar / GJU, Hisar / CDLU, Sirsa / BPS Women University, Khanpur/ DBSCRU, Murthal
5. P.A. to Vice-Chancellor (for kind information of the Vice-Chancellor), M. D. University, Rohtak
6. P.A. to Registrar (for kind information of the Registrar), MDU, Rohtak
7. Divisional Accountant, Engg. Cell, MDU, Rohtak
8. SDE(C-I, II, III) / SDE (Elect.) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
9. H.D.M., Engineering Cell, MDU, Rohtak
10. Notice Board
11. Contractor/Agency/Society: _____

Executive Engineer

DETAILED NOTICE INVITING TENDER

Name of the work “ Construction of 4 nos. Lawn Tennis Courts in the Sports Complex, M.D.U, Rohtak”

App. Amt. Rs. 27,18,000/-
Earnest Money Rs. 27,180/- / Rs. 54,360/-
Time Limit: 04 months

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|-----------|---|--|-------------|
| 1/6.6 | 55.93 cum | Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches , stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction , including disposal of all surplus soil, as directed with in a leadoff 30 meters | @ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only) | Per 100 cum |
| 2/10.26 | 9.31 cum | Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth | @ Rs. 300.20 (Rs. Three hundred & paisa twenty only) | Per cum |
| 3/11.22 | 31.13 cum | 1 st class brick work 1:6 (1 cement : 6 stone dust). Dismantled bricks will be supplied by the Department (@ 3000/- per 1000 nos.) and scrapping will be done by the contractor as per HSR rates. | @ Rs. 413.55 (Rs. Four hundred thirteen and paisa fifty only) | Per cum |
| 4/10.36 | 9.14 cum | Cement concrete 1 : 4 : 8 with brick ballast 40 mm nominal size in foundation and plinth | @ Rs. 385.25 (Rs. Three hundred eighty five and paisa twenty five only) | Per cum |
| 5/24.1 (LR) | 2538 sqm | Preparation of sub grade including trenching rough dressing of spoil, final dressing of earth to given levels and camber watering rolling with road roller and compacting the bed. | @ Rs. 83.00 (Rs. Eighty three only) | Per 100 sqm |
| 6/10.41 | 1.29 cum | Cement concrete 1:2:4 with stone aggregate 20mm nominal size in foundation and plinth. | @ Rs. 615.60 (Rs. Six hundred fifteen and paisa sixty only) | Per cum |
| 7/14.8 | 30 sqm | Conglomerate floor 25 mm thick cement concrete topping 1:2:4 | @ Rs.22.40 (Rs. Twenty two & paisa forty only) | Per sqm |

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|----------------------|-------------|--|--|----------|
| 8/10.82+ 10.95(a) | 3.79 cum | Cement concrete 1:1½:3 instead of cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in slabs with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement, but including centering and shuttering, laid in position, complete in all respects. | @ Rs. 1,084.80 (Rs. One thousand eighty four and paisa eighty only) | Per cum |
| 9/18.22 | 3.41 qtl. | Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete | @ Rs. 917.05 (Rs. Nine hundred seventeen & paisa five only) | Per qtl. |
| 10/15.5 | 186.82 sqm | 12 mm thick cement plaster 1:4 | @ Rs. 12.70 (Rs. Twelve & paisa seventy only) | Per sqm |
| 11/15.10 | 212.65 sqm | 15 mm thick cement plaster 1:4 on the rough side of single or half brick wall | @ Rs. 15.65 (Rs. Fifteen and paisa sixty five only) | Per sqm |
| 12/10.59 + 10.62 | 7.24 cum | Cement concrete 1:2:4 with stone aggregate 20mm nominal size in first storey upto 4 metres above plinth level. Extra over Item no. 10.1 to 10.61 above when work is done in situ in small quantities not exceeding 0.30 cum per block in situ such as staggered blocks, arrows, concrete blocks over inverted filters, bed plates, arches, etc. | @ Rs. 629.85 (Rs. Six hundred twenty nine and paisa eighty five only) | Per cum |
| 13/16.25 | 444.90 sqm | Cement pointing 1:2 flush on flat brick flooring. 1 st quality paint | @ Rs. 4.15 (Rs. Four and paisa fifteen only) | Per sqm |
| 14/16.79(b) | 444.90 sqm | Providing two coats of exterior acrylic emulsion paint. b) 1 st quality. | @ Rs. 48.75 (Rs. Forty eight and paisa seventy five only) | Per sqm |
| 15/N.S. | 1043.45 sqm | Dry stone pitching 75 mm thick including supply of stones and preparing surface complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per sqm |

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|-------------|--|-------------------------------------|---------|
| 16/N.S. | 193.32 cum | Laying water bound macadam sub borne with brick aggregate and binding material earth etc. including screening, sorting and spreading to template and consolidation with light power roller etc. complete. Over burnt jhama brick aggregate 90 mm-45 mm complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per cum |
| 17/N.S. | 241.65 cum | Supply and stacking at site over burnt jhama bricks 90.45 mm complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per cum |
| 18/N.S. | 1043.45 sqm | Providing and laying of special clay 75 mm thick leveled and compacted by hand roller complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per sqm |
| 19/N.S. | 612 cum | Supplying and filling tibba sand including leveling, dressing, watering & consolidation etc. complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per cum |
| 20/N.S. | 2538.40 sqm | Supply, stacking and spreading 6 mm thick red bajri over clay base, watering and rolling complete including preparation of surface and rolling with hard roller complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per sqm |
| 21/N.S. | 2538.40 sqm | Supply, stacking and spreading 25 mm thick moorum complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per sqm |
| 22/N.S. | 2538.40 sqm | Supply, stacking and spreading 12 mm thick fine moorum complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per sqm |
| 23/N.S. | 659.40 sqm | Providing G.I. chain link fencing with 2" dia M.S. pipe frame having 13" long vertical post embedded in cement concrete 1:2:4, 2'-6" deep ditch size 1'-6x1'-6" and 3 nos. runners including provision of gate of same material as per existing pattern complete including priming and painting frame and fencing complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per sqm |
| 24/N.S. | 4 nos. | Providing and fixing of pole post and net of approved specification complete to the entire satisfaction of Engineer-in-Charge.(As per Murthal Univresity) | Rate to be quoted by the contractor | Each |

DETAILED NOTICE INVITING TENDER

Name of the work “Construction of one no. Basket Ball Court and repair of existing Basket Ball Courts in the Sports Complex in M.D.U, Rohtak”

**App. Amt. Rs. 14,42,000/-
Earnest Money Rs. 14,200/- / 28,840/-
Time Limit: 03 months**

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------------|-------------|---|---|-----------------------|
| 1/6.2(a) | 539.09 cum | Earth work excavation in ordinary soil exclusive of compensation of earth: (a) Kassi work undressed involving an average horizontal throw upto 2 metres, and an average vertical lift upto 0.5 metre including breaking of clods | @ Rs.415.50 (Rs. Four hundred fifteen and paisa fifty only) | Per 100 cum |
| 2/10.26 | 150.50 cum | Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth | @ Rs. 300.20 (Rs. Three hundred & paisa twenty only) | Per cum |
| 3/10.132 + 10.95(a) | 69.76 cum | Cement concrete 1: 1½::3 with stone aggregate 20 mm nominal size in pavements, roads, taxi tracks and runways, laid to required slope and camber, including consolidation, finishing and tampering complete | @ Rs. 729.30 (Rs. Seven hundred twenty nine & paisa thirty only) | Per cum |
| 4/14.24 | 1482.13 sqm | Flat brick or tile flooring laid dry over a bed of 6mm thick cement sand mortar 1:6 grouted with cement sand mortar 1:4 and top surface to be left clean after wire brushing. | @ Rs. 32.00 (Rs. Thirty two only) | Per sqm |
| 5/24.34 | 1463 mtr. | Making and filling expansion joints, with bituminous filler (bitumen 40 percent, asbestos 5 percent and sand 55 percent), 12 mm wide | @ 0.35 (Paisa thirty five only) | Per mtr. per cm depth |
| 6/N.S. | 668.88 sqm | Base course of floors consisting of 175 mm thick cement concrete 1:8:16 and 175 mm sand or stone filling complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per sqm |
| 7/N.S. | 694.94 mtr. | Cleaning the joint using hand cutter and blower. Filling the cleaned joint with EPE foam and creating a joint size 10 mm x 5 mm. Repairing all cracks by opening the | Rate to be quoted by the contractor | Per mtr. |

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|------------|--|-------------------------------------|---------|
| | | same and repairing using deco filler. Laying masking tabpe on all the edges before filling sealant. Filling deco seal-G, gun grade, two component sealant, in the prepared joint. Finishing the joint using diesel/soap water as anti sticking agent. Removing the masking tape while the sealant in the joint is still wet complete to the entire satisfaction of Engineer-in-Charge. | | |
| 8/N.S. | 01 job | Carriage of basket ball poles, fibre board, ring net etc. for one basket ball court from University Store/Sports Office complete including erection in proper alignment and painting of poles etc. complete as per direction of Engineer-in-charge. | Rate to be quoted by the contractor | Per job |
| 9/N.S. | 01 job | Marking and painting of borders and shooting D/circle of ground with enamel paint of approved specification complete as direction of Engineer-in-charge. | Rate to be quoted by the contractor | Per job |
| 10/N.S. | 539.09 cum | Disposal of surplus soil/malba/deteriorated earth within the University premises as per direction of Engineer-in-charge including cost of loading, unloading and carriage etc. complete. | Rate to be quoted by the contractor | Per cum |

DETAILED NOTICE INVITING TENDER

Name of the work “Supplying and filling tibba sand after excavation of the existing earth and malba between the boundary wall of Bhagirathi, Krishna Girls Hostel in M.D.U, Rohtak”

**App. Amt. Rs. 14,00,000/-
Earnest Money Rs. 14,200/- / 28,000/-
Time Limit: 02 months**

| Sr. No. / HSR | Qty. | Description | Rate (Rs.) | Unit |
|---------------|-------------|---|-------------------------------------|---------|
| 1/N.S. | 4138.88 cum | Earth work in excavation of all kinds of soil/malba and lifting with in MDU Campus complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per cum |
| 2/N.S. | 8277.75 cum | Supply and filling tibba sand including leveling, dressing and spreading etc. complete to the entire satisfaction of Engineer-in-Charge. | Rate to be quoted by the contractor | Per cum |