

DNIT for the work “Repair of A.C. Units in rear Reading Hall of Vivekananda Library at MDU, Rohtak - - E.I.”

App. Amount : Rs. 96,000/-
Earnest Money : Rs. 1,920/-
Time limit : 15 days

Sr. No.	Qty.	Description	Rate (Rs.)	Unit
1/NS	4 nos.	Supply and erection of Shaft of blower motor (Model No. MPAI 132EMD3, Single phase 220V, 8.5 Amp. 900W) as per entire satisfaction of Engineer-in-Charge.	To be quoted by contractor	Each
2/NS	8 nos.	Supply and erection of Blower Unit without Shaft (Model No. MPAI 132EMD3 cooling capacity-33000 K.Cal/hr, HHLI make- A subsidiary of Hitachi Appliance) as per entire satisfaction of Engineer-in-Charge.	To be quoted by contractor	Each
3/NS	4 nos.	Supply and erection of suction pipe 7/8 “ in U-band as per entire satisfaction of Engineer-in-Charge.	To be quoted by contractor	Each
4/NS	4 nos.	Supply and charging of gas R-22 as per entire satisfaction of Engineer-in-Charge.	To be quoted by contractor	Each
5/NS	60 mtrs.	Supply and erection of 2.5 mm ² x 3 Core PVC copper wire for control wiring as per entire satisfaction of Engineer-in-Charge.	To be quoted by contractor	Per mtr
6/NS	4 nos.	Supply and erection of Drain Tray with nitrile rubber insulation of 9 mm thickness as per entire satisfaction of Engineer-in-Charge.	To be quoted by contractor	Each