

DNIT for the work “P/F power points for racks installed in various hostels (Boys & Girls) at MDU, Rohtak - - E.I.”

App. Amount : Rs. 1,73,000/-
Earnest Money : Rs. 3,460/-
Time limit : 01 month

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/31.17	46 nos.	Miniature Circuit Breaker and Isolator: Supply and erection of miniature circuit breaker/isolator 240 / 415 V in the existing distribution board including making necessary connections:- (a) Miniature Circuit Breakers of 9 K.A. breaking capacity. (ii) 6 amp. to 32 amp. (Single Pole)	@ Rs. 95.00 (Rs. Ninety five only)	Each
2/31.21	250 mtrs. 150 mtrs.	Pipe Laying: Supply and erection of pipe for wiring purposes (including bends inspection boxes etc. where necessary and painting as required :- (xvi) Heavy Gauge welded conduit pipe 25 mm dia 1.60 mm thickness on surface. (xxii) Heavy gauge welded conduit pipe 25 mm dia 1.6 mm thickness flushed	@ Rs. 18.40 (Rs. Eighteen and forty paise) @ Rs. 19.60 (Rs. Nineteen and sixty paise)	Per mtr. Per mtr.
3/31.40	1200 mtrs. 2500 mtrs.	Supply and erection of PVC unsheathed copper conductor cable single core 1100 volts grade in pipe of suitable size excluding cost and erection of pipe. (i) Cable size 1.5 sqmm (3/0.81mm) (ii) Cabl size 4 sqmm (7/0.85mm)	@ Rs. 10.20 (Rs. Ten and paise twenty only) @ Rs. 24.50 (Rs. Twenty four and paise fifty only)	Per mtr. Per mtr

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
4/31.44	150 mtrs.	Supply and erection of PVC conduit pipe ISI marked (Medium) recessed in wall/ceiling etc. including cost of PVC bends, inspection box and all other material required to complete the job in all respect up to the entire satisfaction of Engineer-in-Charge of work. (b) 25mm dia	@ Rs. 37.00 (Rs. Thirty seven only)	Per mtr.
5/31.48	1500 nos.	Supply and erection of MS saddles and clamps on wall/RCC parapet for fixing underground cable at a distance of 0.60 metre centre to centre fixed by means of rawl plug including the cost of all labour and material required to complete the job in all respect.	@ Rs. 5.00 (Rs. five only)	Each
6/31.56	46 nos.	Providing and fixing modular type accessories of approved make in existing box including fixing and making necessary connection, complete in all respects. (iii) 20 amp. switch	@ Rs. 116.00 (Rs. One hundred and sixteen only)	Each
	46 nos.	(v) 16 amp. Socket	@ Rs. 165.00 (Rs. One hundred sixty five only)	Each
7/31.57	46 nos.	Providing and fixing GI concealed sheet metal boxes with inner and outer faceplate including concealing the box in all and fixing in position with inner plate and face plate with all labour and material required for the job complete in all respects. (ii) 3 Modules	@ Rs. 128.00 (Rs. One hundred twenty eight only)	Each

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/N.S.	250 mtrs.	Supply and erection of PVC pipe 25 mm on surface medium up to the satisfaction of Engineer-in-charge.	Rates to be quoted by the contractor	Per mtr.

- Note :
1. The underground cable will be used of Havells / Polycabe make No extra payment will be allowed on this account.
 2. PVC pipe of 6 Kg. pressure Kasta / Swastik / Supreme make of HSR item no. 31.21 will be used. No extra payment will be allowed on this account.
 3. The material used for HSR Item no. 31.12, 31.15, 31.17 and 31.41 will be used of Standard/ Havells make and no extra payment will be allowed on this account.
 4. PVC copper wire 31.38, 31.39 and 31.40 will be used of Plaza/ Havells/ Polycabe make and no extra payment will be allowed on this account.