DETAILED NOTICE INVITING TENDER

Name of the work "Development of Horticulture work in the New Park in front of Type-I and Type IA houses in M.D.U, Rohtak"

App. Amt. Rs. 4,30,000/-Earnest Money Rs. 4,300/- / Rs. 8,600/-Time Limit: 02 months

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/33.1	100 cum	Supplying at site of work well-decayed farm-yard manure, from any available source, approved by the Engineer-in-charge including screening and stacking	<pre>@ Rs.61.60 (Rs. Sixty one and paisa sixty only)</pre>	Per cum
2/33.7 (LR)	12300 Sqm	Fine dressing the ground	@ Rs.12.90 (Rs. Twelve and paisa ninety only)	Per 100 Sqm.
3/33.21 (LR)	100 N	Digging holes in all kinds of soil, and refilling the same, with the excavated earth, mixed with well decayed farm- yard manure (cost of well decayed farm yard manure to be paid separately)	@ Rs.16.80	Each
	100 Nos. 200 Nos.	(i) hole 1.2 metres dia and 1.2 metres deep(ii) hole 0.60 metre dia and 0.60 metre deep	(Rs. Sixteen and paisa eighty only) @ Rs. 2.40 (Rs. Two and paisa forty only)	Each
4/33.19 (LR)	1710 Running mtr.	Planting permanent hedges including digging of trenches, 60 cm wide and 45 cm deep, refilling the excavated earth, mixed with farm-yard manure, supplied at the rate of 4.65 cu pr 100 metres and supplying and planting hedge plants at 30 cm apart	@ Rs.2,278.35 (Rs. Two thousand two hundred seventy eight and paisa thirty five	Per 100 Running mtr.
5/33.17 (LR)	12300 Sqm	Turfings lawns with fine grassing including ploughing, dressing including breaking of clods, removal of rubbish, dressing and supplying doob grass roots at 10 cm apart, including supplying and spreading of farm-yard manure at the rate of 0.60 cum per 100 sqm.	@ Rs. 155.85 (Rs. One hundred fifty five and paisa eighty five only)	Per 100 Sqm
6/N.S.		Providing of shady trees and ornamental plants complete to the entire satisfaction of Engineer-in-Charge		
	100 Nos.	Shady Tree 5' height	Rate to be quoted by the contractor	Each
	200 Nos.	Ornamental plants	Rate to be quoted by the contractor	Each