

DETAILED NOTICE INVITING TENDER

Name of the work “Providing and fixing Shed in Dholagiri Hostel and Extension of main Shed in Udaigiri Boys Hostel in M.D.U, Rohtak”

**App. Amt. Rs. 1,30,000/-
Earnest Money Rs. 1,300/- / Rs. 2,600/-
Time Limit: 01 months**

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/18.41	4.39 qtl.	Providing steel pipe ISI mark in columns with 2 nos. M.S. plates welded on both ends of the pipe including cutting etc. complete fixed in position.	@ Rs. 1,205.35 (Rs. One thousand two hundred five and paise thirty five only)	Per qtl.
2/18.12	4.175 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors openable or fixed stair case or parapet or any other type of railing, gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1,040.35 (Rs. One thousand forty & paise thirty five only)	Per qtl
3/13.20	131.92 sqm	Corrugated asbestos sheet roofing 6mm thick sheet fixed with G.I. hooks and bolts, limpet and bitumen washers complete, fixed in position, excluding the cost of purling, rafters and trusses.	@ Rs. 73.50 (Rs. Seventy three and paise fifty only)	Per sqm
4/11.8	2.37 cum	First class brick work laid in cement sand mortar 1:5 in first storey upto 4 metres above plinth level.	@ Rs. 428.60 (Rs. Four hundred twenty eight and paise sixty only)	Per cum
5/15.6	22.20 sqm	12mm thick cement plaster 1:4	@ Rs. 11.60 (Re. Eleven and paise sixty only)	Per sqm
6/10.41	0.42 cum	Cement concrete 1:2:4 with stone aggregate 20 mm nominal size in foundation and plinth	@ Rs. 615.60 (Rs. Six hundred fifteen & paise sixty only)	Per cum
7/16.25	437.38 sqm	Applying priming coat with cement primer in all shades on newly plastered or concrete exterior surfaces	@ Rs. 4.15 (Rs. Four and paise fifteen only)	Per sqm
8/16.79(b)	437.38 sqm	Providing two coats of exterior acrylic emulsion paint. b) 1 st quality.	@ Rs. 48.75 (Rs. Forty eight and paise seventy five only)	Per sqm

Contnd. Next Page

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
9/N.S.	720 sft.	Dismantling of G.I. sheet shed complete to the entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per sft.