



MAHARSHI DAYANAND UNIVERSITY ROHTAK

(A State University established under Haryana Act No. 25 of 1975)

NAAC accredited 'A' Grade

NOTICE INVITING TENDER

Sealed tenders on percentage basis are invited on behalf of the Registrar, MDU, Rohtak from contractors/societies / agencies on approved list of PWD, MES, CPWD, autonomous bodies and State / Centre Govt. undertakings. The tender forms will be issued to the contractors / societies agencies / up to the date of opening of tenders as mentioned against work by 12:00 Noon and will be received up to 2:00 P.M. in the office of the Registrar and opened at 3:00 P.M. on the same day in the Committee Room of Vice-Chancellor office in the presence of the tenderers or their authorized representatives, who may like to be present at that time. **The tender documents may be obtained from the office of the undersigned and the same be deposited in the office of the Registrar by the due date.**

Sr. No.	Name of work	App. Amt. (Rs.)	Earnest Money (Rs.)		Cost of tender form (Rs.)	Date of opening of tender	Time limit
			Society	Contractor			
1.	Providing and fixing wire mesh in balcony of rooms at ground floor, 1 st floor and 2 nd floor in Saraswati Girls Hostel in MDU, Rohtak	11,99,000/-	11,990/-	23,980/-	1,000/-	21.03.2014	04 months
2.	Dismantling of damaged chowkhats & shutters and providing & fixing new chowkhats & shutters in Saraswati Girls Hostel in MDU, Rohtak	8,47,000/-	8,470/-	16,940/-	1,000/-	21.03.2014	04 months
3.	Providing and fixing cupboard chowkhats & shutters in Saraswati Girls Hostel in MDU, Rohtak	8,07,000/-	8,070/-	16,140/-	1,000/-	21.03.2014	04 months
4.	Reconstruction/repair of damaged open drain at various places in MDU, Rohtak	7,39,000/-	7,390/-	14,780/-	1,000/-	21.03.2014	03 months

CONDITIONS:-

1. Complete NIT / DNIT (Detailed Notice Inviting Tender) alongwith eligibility criteria/terms & conditions and changes if any can be seen in the office of undersigned on any working day during office hours (9:00 AM to 5:00 PM) or on University Website – www.mdurohtak.ac.in
2. The tenderer will keep in touch with the University Web site for any change in the NIT / DNIT till the last date/revised last date of sale of tender and incorporate such changes in NIT / DNIT and the tender bids.
3. At the time of purchase of tender documents, the contractors should submit the following documents:-
 - (a) Proof of enlistment.
 - (b) Copy of PAN card.

(c) Copy of latest income tax return.

(d) Successfully work done certificates of civil works during last 5 years (financial year 2009-10 to 2013-14) as under:-

One certificate of 80% of the estimated cost of this tender.

Or

Two certificates of 60% of the estimated cost of this tender

Or

Three certificates of 40% of the estimated cost of this tender

All the above certificates in paras 3(a) to 3(d) above will be self attested with stamp.

4. In case tendering receiving / opening day happens to be a holiday, the tenders will be received / opened on next working day at the same time.
5. Validity of tender will be 90 days.
6. Earnest money is to be deposited at the time of purchase of the tender. It should be in the shape of Demand Draft or Deposit at Call in favour of the Executive Engineer, MDU, Rohtak payable at Rohtak.
7. Contractors shall quote percentage of rate below/above/at par on (HSR+C.P.) on all items of DNIT separately. The N.S. item rates are to be quoted separately. The tender, without item wise rate in DNIT, will be rejected.
8. Conditional tender is liable to be rejected.
9. Any work, here tendered, may be withdrawn from further processing at any stage at the discretion of the competent authority without assigning any reason.
10. Engineer-in-Charge is competent to increase / decrease the quantity of work. In case of decrease of quantity, the contractor shall have no claim to any payment or compensation whatsoever on account of any profit or advantage which he might have derived from the execution of the work in full.
11. Nothing extra whatsoever shall be paid on account of losses, damages done by rains or any other natural calamity.
12. The tender is liable to be rejected if the tender is found in variance of the above conditions or the conditions of the DNIT.
13. The University reserves the right to accept or reject or negotiate any of the tender or conditions/items without assigning any reason.
14. Plumbing and E.I. work shall be got done through license holder agencies for the works involving PH / E.I.
15. The agencies shall paste the cello tape on the rates quoted by them.
16. Tender by post / telegraphic/courier shall out rightly be rejected.
17. Exemption of tender fee or earnest money or security will not be permitted in any case.

Executive Engineer

A copy of the pre-page is forwarded to the following for information and necessary action:-

1. Superintending Engineer, PWD B&R Circles, Rohtak
2. Technical Advisor to VC, MDU, Rohtak
3. Executive Engineer(C-II), MDU, Rohtak
4. Executive Engineer, PWD B&R (Medical College), Rohtak / KUK / HAU. Hisar / GJU, Hisar / CDLU, Sirsa / BPS Women University, Khanpur/ DBSCRU, Murthal
5. P.A. to Vice-Chancellor (for kind information of the Vice-Chancellor), M. D. University, Rohtak
6. P.A. to Registrar (for kind information of the Registrar), MDU, Rohtak
7. Divisional Accountant, Engg. Cell, MDU, Rohtak
8. SDE(C-I, II, III) / SDE (Elect.) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
9. H.D.M., Engineering Cell, MDU, Rohtak
10. Notice Board
11. Contractor/Agency/Society: _____

Executive Engineer

DETAILED NOTICE INVITING TENDER

Name of the work “Providing and fixing wire mesh in balcony of room at ground floor, 1st floor and 2nd floor in Saraswati Girls Hostel in M.D.U, Rohtak”

**App. Amt. Rs. 11,99,000/-
Earnest Money Rs. 11,990/- / Rs. 23,980/-
Time Limit: 04 months**

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/18.12	87.87 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors open-able or fixed stair case or parapet or any other type of railing , gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1040.35 (Rs. One thousand forty & paisa thirty five only)	Per qtl
2/18.32	1032.79 sqm	Wire gauze of 140 G or 120 G designation fixed on steel windows of standard rolled steel section with 3mm thick flat iron cover moulding of 12.5 mm width, fixed with machine screws welded complete in all respects.	@ Rs. 99.10 (Rs. Ninety nine and paisa ten only)	Per sqm
3/18.33	26.42 sqm	Providing and fixing hard drawn steel wire fabric 75mm x 25mm rectangular mesh with 3.25 mm dia wire fixed on steel windows of standard rolled sections with 3mm thick flat iron cover moulding of 12.5 mm width fixed with machine screws welded complete in all respects.	@ Rs. 104.10 (Rs. One hundred four and paisa ten only)	Per sqm
4/16.3	750 sqm	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	@ Rs. 8.05 (Rs. Eight & paisa five only)	Per sqm

DETAILED NOTICE INVITING TENDER

Name of the work “Dismantling of damaged chowkhats & shutters and providing & fixing new chowkhats & shutters in Saraswati Girls Hostel, M.D.U, Rohtak”

**App. Amt. Rs. 8,47,000/-
Earnest Money Rs. 8,470/- Rs. 16,940/-
Time Limit: 04 months**

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/8.18(a)	218 nos.	Removing doors and windows (wooden and steel) together with the dismantling of walls when the wall is not to be dismantled:- (a) door	@ Rs. 11.90 (Rs. Eleven and paisa ninety only)	Each
2/18.34	73.72 mtr. 326.90 mtr.	Pressed steel sheet frames (chowkhats) consisting of 2 mm thick steel sheet of the specified section, including iron lugs (hold fasts), iron hinges, conforming to PWD specifications, including bolts for fixing stops lockmotch, provision for receiving tower bolts and finished with one coat of ready-mixed paint red lead non setting primer, of approved quality, fixed in position including the cost of cement concrete 1:3:6 for filling in the frame and cement concrete 1:3:6 for lugs complete:- (a) door & window frames of size 89 mm x 50 mm with 40 mm wide single rebate. (c) door & window frames of size 127 mm x 50 mm with 40 mm wide single rebate	@ Rs. 71.55 (Rs. Seventy one & paisa fifty five only) @ Rs. 76.80 (Rs. Seventy six and paisa eighty only)	Per mtr. Per mtr.
3/18.12	10.51 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard, iron doors open-able or fixed stair case or parapet or any other type of railing, gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1040.35 (Rs. One thousand forty & paisa thirty five only)	Per qtl.
4/17.93 (a) (iii) - (Note 17.18)		Factory manufacture solid flush door shutter with block board core as per I.S. no. 1659-1969 boarded with water proof type phenol formaldehyde synthetic resin hot		

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
	58.53 sqm	pressed conforming to IS 2202 part-I and part II, fixed in position, including iron hinges, screws, chocks/cleats and stops etc (excluding the cost of any fittings other than specified above , but including labour for fixing the same in position) (a) commercial veneering with vertical grains or cross bands and face veneer on both sides commercial facing with laminated core and lipped edges:- (i) 25 mm thick	@ Rs. 387.15 (Rs. Three hundred eighty seven and paisa fifteen only)	Per sqm
	158.25sqm	(iii) 35mm thick NOTE: The door will be of DURO/CENTURY make only	@ Rs. 436.15 (Rs. Four hundred thirty six and paisa fifteen only)	Per sqm
5/17.92	110.01sqm	Factory manufactured wire gauze door and window, shutters of commercial hard wood such as hollock, champ, chikrassy and chaplash etc. (non coniferous timber other than teal , conforming to I.S. specification No.1003, kiln seasoned) with 100 mm wide vertical styles, 150 mm wide lock rail, 200 mm wide bottom rail and wire gauze of 140 G or 120 G designation including cost of iron hinges, screws, chock/cleats, stops nails etc., complete fixed in position (excluding the cost of any fittings, other than specified above but including labour for fixing the same in position (i) 35mm thick	@ Rs. 347.55 (Rs. three hundred forty seven and paisa fifty five only)	Per sqm
6/16.2+16.3 + 16.1	769.90 sqm	Applying pink primer or aluminum priming coat on wood work including preparation of surface, knotting and stopping etc.	@ Rs. 16.25 (Rs. Sixteen and paisa twenty five only)	Per sqm
7/N.S.	70.23 sqm.	Providing and fixing P.V.C door shutters with chowkhat complete to the entire satisfaction of Engineer-in-Charge	Rate to be quoted by the contractor	Per sqm

DETAILED NOTICE INVITING TENDER

Name of the work “Providing and fixing cupboard, chowkhats & shutters in Saraswati Girls Hostel in M.D.U, Rohtak”

App. Amt. Rs. 8,07,000/-

Earnest Money Rs. 8,070/- / Rs. 16,140/-

Time Limit: 04 months

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/11.48(a)	239.13 sqm	(a) 11.43 cm thick brick wall laid in cement sand mortar 1:4 in superstructure (i) 2 nd storey	@ Rs. 56.05 (Rs. Fifty six and paisa five only)	Per sqm
2/18.12	30.86 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard , iron doors openable or fixed stair case or parapet or any other type of railing , gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1,040.35 (Rs. One thousand forty & paisa thirty five only)	Perqtl.
3/10.81	14.90 cum	Cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in Shelves excluding steel reinforcement, but including centering and shuttering, laid in position, complete in all respects.	@ Rs. 955.00 (Rs. Nine hundred fifty five only)	Per cum
4/18.22	14.90 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. Nine hundred seventeen & paisa five only)	Per qtl.
5/17.93(a) (i)	219.20 sqm	Factory manufacture solid flush door shutter with block board core as per I.S. no. 1659-1969 bonded with water proof type phenol formaldehyde synthetic resin hot pressed conforming to IS 2202 part-I and part II, fixed in position, including iron hinges, screws, chocks/cleats and stops etc (excluding the cost of any fittings other than specified above , but including labour for fixing the same in position) (a) commercial veneering with vertical grains or cross bands . (i) 25mm thick NOTE: The door will be of DURO/CENTURY make only	@ Rs. 387.16 (Rs. Three hundred eighty seven and paisa sixteen only)	Per sqm

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
6/17.72(b)	219.20 sqm	Cost of aluminum fittings complete for doors and windows , such as tower bolts, handles, etc and screws for these fittings (excluding sliding bolts) (b) for double leaf shutter	@ Rs. 27.45 (Rs. Twenty seven and paisa forty five only)	Per sqm
7/17.78(b)	312 nos.	Providing and fixing 150mm hasps and staples with necessary screws, etc., complete. (b)Aluminium	@ Rs. 10.35 (Rs. Ten and paisa thirty five only)	Each
8/15.10	746.36 sqm	15 mm thick cement plaster 1:4 on the rough side of single or half brick wall	@ Rs. 15.83 (RS. Fifteen & paisa eighty threeonly)	Persqm
9/16.1+16.2 + 16.3	526.08sqm	Preparation of ply wood surface for painting including sand papering the surface and applying filling with approved quality filler consisting of white lead, linsed oil, varnish and chalk mitti including finishing the surface to required/finish complete	@ Rs. 16.25 (Rs. Sixteen & paisa twenty five only)	Per sqm

DETAILED NOTICE INVITING TENDER

Name of the work “Reconstruction / repair of damaged open drain at various places in M.D.U, Rohtak”

App. Amt. Rs. 7,39,000/-

Earnest Money Rs. 7,390/- / Rs. 14,780/-

Time Limit: 03 months

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/6.6	195.84 cum.	Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches , stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction , including disposal of all surplus soil, as directed with in a leadoff 30 meters	@ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only)	Per % cum
2/10.28	22.95 cum.	Cement concrete 1:8:16 with stone aggregate 40mm nominal size in foundation and plinth.	@ Rs. 318.65 (Rs. three hundred eighteen and paisa sixty five only)	Per cum
3/11.9	192.25 cum.	1 st class brick work laid in cement sand mortar 1:4 in first storey upto 4 metres above plinth level.	@ Rs.445.60 (Rs . four hundred forty five and paisa sixty only)	Per cum
4/15.5+15.75	511.82 sqm	12 mm thick cement plaster 1:4. and rendering on plaster 1mm thick.	@ Rs. 16.95 (Rs. Sixteen and paisa ninety five only)	Per sqm
5/14.8	74.41 sqm.	Conglomerate floor 25 mm thick cement concrete topping 1:2:4	@ Rs.22.40 (Rs. twenty two & paisa twenty two only)	Per sqm
6/15.10	75.14 sqm.	15 mm thick cement plaster 1:4 on the rough side of single or half brick wall	@ Rs. 15.65 (RS. Fifteen & paisa sixty five only)	Per.sqm
7/8.32(e)	18580 nos.	Scraping: (e) brick dismantled from brick work in lime or cement	@ Rs. 83.10 (Rs. eighty three and paisa ten only)	Per 1000 nos.
8/N.S.	73 nos.	Providing and fixing P.V.C. pipe with cap casta / suprim make 4’’ dia 6 kg preausre complete to the entire satisfaction of Engineer-in-Charge	Rate to be quoted by the Contractor	Each

Note:- 1. Credit of old bricks from dismantled drain will be recovered from the contractor @ Rs. 5000/- per 1000 nos.

2. Credit of brick bats from dismantled drain will be recovered from the contractor @ Rs 600/- per cum.